BRUHAT BANGALORE MAHANAGARA PALIKE
PROJECT DIVISION, YELAHANKA ZONE

Name of Work:- Improvements to widen portion of roads,construction of new drains,UG cable duct and footpath at Doddabommasandra main road surrounding road in ward No.10

ame of Agency :- Sri. Gopikrishna Apsani (Nidhi Constructions)

ob Code :- 010-16-000032

Modified Estimate

OQ Item No	Description / Chainage	Side	Nos	Length	Width B1	Width B2	Width Avg B	Depth	Quantity	Unit/ Remarks	Rate	Amount
1	KSRRB M300-14. Excavation for roadwork in all types of soil with hydraulic excavator of 0.9 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transporting to the embankment location to a lead of 1.00 km and complete as per specifications. MORTH Specification No.301(pg no-143,S.Lno-19.14)KPWD S.R 2018-19											
	Virupakshanagar 5th cross road.											
	0.00 15.00		1	15.00	6.80	5.90	6.35	0.30	28.58			
	15.00 30.00		1	15.00	5.90	5.90	5.90	0.30	26.55			
	30.00 45.00		1	15.00	5.90	5.80	6.00	0.30	27.00			
	45.00 60.00		1	15.00	6.30	5.80	6.05	0.30	27.23			
	60.00 75.00		1	15.00	5.80	5.40	5.60	0.30	25.20			
	75.00 90.00		1	15.00	5.40	5.40	6.00	0.30	27.00			
	90.00 105.00		1	15.00	5.40	5.70	5.55	0.30	24.98			
	105.00 120.00		1	15.00	5.70	5.70	5.70	0.30	25.65			
	120.00 135.00		1	15.00	5.70	5.60	5.65	0.30	25.43			
	135.00 150.00		1	15.00	5.60	5.60	5.60	0.30	25.20			
	150.00 165.00		1	15.00	5.60	4.90	5.25	0.30	23.63			
	165.00 180.00		1	15.00	4.90	4.90	4.90	0.30	22.05			
	180.00 195.00		1	15.00	4.90	5.20	5.05	0.30	22.73			
	195.00 210.00		1	15.00	5.20	5.20	5.20	0.30	23.40			
	210.00 214.00		1	4.00	5.20	5.30	5.25	0.30	6.30			
	Virupakshanagar 4th cross road.											
	0.00 15.00		1	15.00	6.10	6.30	6.20	0.30	27.90			
	15.00 30.00		1	15.00	6.30	6.30	6.30	0.30	28.35			
	30.00 45.00		1	15.00	6.30	5.90	6.00	0.30	27.00			
	45.00 60.00		1	15.00	6.30	5.90	6.10	0.30	27.45			
	60.00 75.00		1	15.00	5.90	5.30	5.60	0.30	25.20			
	75.00 90.00		1	15.00	5.30	5.30	6.00	0.30	27.00			
	90.00 105.00		1	15.00	5.30	4.60	4.95	0.30	22.28			
	105.00 120.00		1	15.00	4.60	4.60	4.60	0.30	20.70			
	120.00 135.00		1	15.00	4.60	4.30	4.45	0.30	20.03			
	135.00 150.00		1	15.00	4.30	4.30	4.30	0.30	19.35			
	150.00 165.00		1	15.00	4.30	4.40	4.35	0.30	19.58			
	165.00 180.00		1	15.00	4.40	4.40	4.40	0.30	19.80			
	180.00 195.00		1	15.00	4.40	4.60	4.50	0.30	20.25			
	195.00 208.00		1	13.00	4.60	4.60	4.60	0.30	17.94			
	Virupakshanagar 3rd cross road.											
	0.00 15.00		1	15.00	8.10	6.40	7.25	0.30	32.63			
	15.00 30.00		1	15.00	6.40	6.40	6.40	0.30	28.80			
	30.00 45.00		1	15.00	6.40	5.60	6.00	0.30	27.00			
	45.00 60.00		1	15.00	6.30	5.60	5.95	0.30	26.78			
	60.00 75.00		1	15.00	5.60	5.20	5.40	0.30	24.30			
	75.00 90.00		1	15.00	5.20	5.20	6.00	0.30	27.00			
	90.00 105.00		1	15.00	5.20	5.90	5.55	0.30	24.98			
	105.00 120.00		1	15.00	5.90	5.90	5.90	0.30	26.55			
	120.00 135.00		1	15.00	5.90	5.50	5.70	0.30	25.65			
	135.00 150.00		1	15.00	5.50	5.50	5.50	0.30	24.75			
	150.00 165.00		1	15.00	5.50	5.20	5.35	0.30	24.08			
	165.00 180.00		1	15.00	5.20	5.20	5.20	0.30	23.40			

BOQ Item No	Description Chainage		Side	Nos	Length	Width B1	Width B2	Width Avg B	Depth	Quantity	Unit/ Remarks	Rate
	180.00	195.00		1	15.00	5.20	8.20	6.70	0.30	30.15		
	195.00	210.00		1	15.00	8.20	8.20	8.20	0.30	36.90		
	210.00	225.00		1	15.00	8.20	6.20	7.20	0.30	32.40		
	225.00	240.00		1	15.00	6.20	6.20	6.20	0.30	27.90		
	240.00	255.00		1	15.00	6.20	6.30	6.25	0.30	28.13		
	255.00	270.00		1	15.00	6.30	6.30	6.30	0.30	28.35		
	270.00	285.00		1	15.00	6.30	7.50	6.90	0.30	31.05		
	285.00	300.00		1	15.00	7.50	7.50	7.50	0.30	33.75		
	300.00	308.00		1	8.00	7.50	7.50	7.50	0.30	18.00		
	308.00	310.00		0	0.00	0.00	0.00	0.00	0.00	0.00	culvert	
	310.00	325.00		1	15.00	0.00	7.30	3.65	0.30	16.43		
	325.00	330.00		1	5.00	7.30	7.30	7.30	0.30	10.95		
	3rd C cross Road Yarappa Garden											
				1	14.00	4.90	4.50	4.70	0.35	23.03		
	2nd Cross Road Gas Godown Road											
				1	8.00	2.50	2.50	2.50	0.35	7.00		
				1	12.00	1.20	1.20	1.20	0.35	5.04		
				1	5.00	1.20	1.20	1.20	0.35	2.10		
				1	11.00	2.50	2.50	2.50	0.35	9.63		
				1	6.00	0.90	0.90	0.90	0.35	1.89		
	Edge Restoration											
	Telicom Layout 4th Cross Road											
	LHS											
	0.00	13.50		1	13.50	0.80	1.00	0.90	0.35	4.25		
	13.50	15.00		1	1.50	0.80	1.00	0.90	0.35	0.47		
	15.00	16.00		1	1.00	0.75	0.90	0.83	0.35	0.29		
	16.00	30.00		1	14.00	0.90	1.00	0.95	0.35	4.66		
	30.00	45.00		1	15.00	0.75	1.00	0.88	0.35	4.59		
	45.00	59.00		1	14.00	0.90	0.80	1.00	0.35	4.90		
	59.00	60.00		1	1.00	0.80	0.60	0.70	0.35	0.25		
	60.00	63.00		1	3.00	0.60	0.60	0.60	0.35	0.63		
	63.00	75.00		1	12.00	0.60	0.75	0.68	0.35	2.84		
	75.00	78.00		1	3.00	0.60	1.00	0.80	0.35	0.84		
	110.00	115.00		1	5.00	0.80	1.00	0.90	0.35	1.58		
	115.00	125.00		1	10.00	0.80	1.00	0.90	0.35	3.15		
	151.50	160.00		1	8.50	1.50	1.50	1.50	0.35	4.46		
	160.00	171.50		1	11.50	0.60	1.00	0.80	0.35	3.22		
	Telicom Layout 4th Cross Road											
	RHS											
	0.00	13.50		1	13.50	0.90	0.75	0.83	0.35	3.90		
	16.00	30.00		1	14.00	0.90	0.90	0.90	0.35	4.41		
	30.00	45.00		1	15.00	0.60	0.90	0.75	0.35	3.94		
	45.00	59.00		1	14.00	0.75	0.90	0.83	0.35	4.04		
	63.00	75.00		1	12.00	0.75	0.80	0.78	0.35	3.26		
	75.00	78.00		1	3.00	0.80	0.90	0.85	0.35	0.89		
	78.00	85.00		1	7.00	0.80	1.00	0.90	0.35	2.21		
	98.00	105.00		1	7.00	0.90	1.00	0.95	0.35	2.33		
	105.00	110.00		1	5.00	0.80	1.00	0.90	0.35	1.58		
	110.00	115.00		1	5.00	0.90	1.00	0.95	0.35	1.66		
	125.00	133.00		1	8.00	0.80	1.00	0.90	0.35	2.52		
	2nd Main Road Telicom Layout											
	LHS											
	78.00	90.00		1	12.00	1.00	0.90	0.95	0.35	3.99		
	90.00	91.00		1	1.00	1.00	1.00	1.00	0.35	0.35		
	91.00	105.00		1	14.00	1.00	1.00	1.00	0.35	4.90		
	105.00	109.00		1	4.00	1.00	1.00	1.00	0.35	1.40		
	126.00	135.00		1	9.00	1.00	1.00	1.00	0.35	3.15		
	135.00	143.50		1	8.50	0.90	1.00	0.95	0.35	2.83		
	143.50	150.00		1	6.50	0.90	0.90	0.90	0.35	2.05		
	150.00	165.00		1	15.00	0.90	0.90	0.90	0.35	4.73		
	165.00	180.00		1	15.00	0.90	0.90	0.90	0.35	4.73		
	180.00	185.00		1	5.00	1.00	1.00	1.00	0.35	1.75		

Description		Side	Nos	Length	Width			Depth	Quantity	Unit/ Remarks	Rate	Amount
Chainage					B1	B2	Avg B					
185.00	195.00		1	10.00	1.00	1.00	1.00	0.35	3.50			
195.00	208.00		1	13.00	1.00	1.00	1.00	0.35	4.55			
208.00	210.00		1	2.00	1.00	1.00	1.00	0.35	0.70			
210.00	220.00		1	10.00	1.00	1.00	1.00	0.35	3.50			
220.00	225.00		1	5.00	1.00	1.00	1.00	0.35	1.75			
225.00	240.00		1	15.00	1.00	1.00	1.00	0.35	5.25			
240.00	245.00		1	5.00	1.00	1.00	1.00	0.35	1.75			
253.00	255.00		1	2.00	0.90	0.90	0.90	0.35	0.63			
255.00	270.00		1	15.00	0.90	0.90	0.90	0.35	4.73			
270.00	285.00		1	15.00	0.90	0.90	0.90	0.35	4.73			
285.00	300.00		1	15.00	0.90	0.90	0.90	0.35	4.73			
300.00	315.00		1	15.00	1.00	1.00	1.00	0.35	5.25			
315.00	330.00		1	15.00	1.00	1.00	1.00	0.35	5.25			
330.00	345.00		1	15.00	1.00	1.00	1.00	0.35	5.25			
345.00	360.00		1	15.00	1.00	1.00	1.00	0.35	5.25			
360.00	375.00		1	15.00	1.00	1.00	1.00	0.35	5.25			
375.00	390.00		1	15.00	1.00	1.00	1.00	0.35	5.25			
390.00	405.00		1	15.00	1.00	1.00	1.00	0.35	5.25			
405.00	417.00		1	12.00	0.80	0.90	0.85	0.35	3.57			
2nd Main Road Telicom Layout												
RHS												
78.00	90.00		1	12.00	1.00	1.20	1.10	0.35	4.62			
90.00	91.00		1	1.00	0.80	0.75	0.78	0.35	0.27			
143.50	150.00		1	6.50	0.80	0.60	0.70	0.35	1.59			
150.00	165.00		1	15.00	0.60	1.20	0.90	0.35	4.73			
165.00	180.00		1	15.00	0.60	1.00	0.80	0.35	4.20			
180.00	185.00		1	5.00	0.60	1.00	0.80	0.35	1.40			
240.00	245.00		1	5.00	0.60	1.20	0.90	0.35	1.58			
245.00	250.00		1	5.00	0.60	1.00	0.80	0.35	1.40			
UGD Restoration												
Ganesh Nagar Road												
0.00	15.00		1	15.00	1.20	1.20	1.20	0.35	6.30			
15.00	30.00		1	15.00	1.20	1.20	1.20	0.35	6.30			
30.00	45.00		1	15.00	1.20	1.20	1.20	0.35	6.30			
45.00	60.00		1	15.00	1.20	1.20	1.20	0.35	6.30			
60.00	75.00		1	15.00	1.20	1.20	1.20	0.35	6.30			
75.00	90.00		1	15.00	1.20	1.20	1.20	0.35	6.30			
90.00	105.00		1	15.00	1.20	1.20	1.20	0.35	6.30			
105.00	120.00		1	15.00	1.20	1.20	1.20	0.35	6.30			
120.00	135.00		1	15.00	1.20	1.20	1.20	0.35	6.30			
135.00	150.00		1	15.00	1.20	1.20	1.20	0.35	6.30			
150.00	165.00		1	15.00	1.20	1.20	1.20	0.35	6.30			
165.00	180.00		1	15.00	1.20	1.20	1.20	0.35	6.30			
180.00	195.00		1	15.00	1.20	1.20	1.20	0.35	6.30			
195.00	210.00		1	15.00	1.20	1.20	1.20	0.35	6.30			
210.00	225.00		1	15.00	1.20	1.20	1.20	0.35	6.30			
225.00	240.00		1	15.00	1.20	1.20	1.20	0.35	6.30			
240.00	255.00		1	15.00	1.20	1.20	1.20	0.35	6.30			
255.00	270.00		1	15.00	1.20	1.20	1.20	0.35	6.30			
270.00	285.00		1	15.00	1.20	1.20	1.20	0.35	6.30			
285.00	300.00		1	15.00	1.20	1.20	1.20	0.35	6.30			
300.00	315.00		1	15.00	1.20	1.20	1.20	0.35	6.30			
315.00	330.00		1	15.00	1.20	1.20	1.20	0.35	6.30			
330.00	338.50		1	8.50	1.20	1.20	1.20	0.35	3.57			
								TOTAL QTY	**1677.09**			
								BOQ	**1574.49**			
								Qty Upto 125%	**1677.09**	Cum	120.81	**202609.24**

BOQ Item No	Description / Chainage		Side	Nos	Length	Width B1	Width B2	Width Avg B	Depth	Quantity	Unit/ Remarks	Rate
2	Construction of granular sub-base Grading-V as sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/trap/basalt material, mixing in a mechanical mix plant at OMC, carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98% proctor density, complete as per specifications. Clause 401 of MORTH V Revision.GSB Page No. 153/ Item No. 20.5/ PWD SR 2018-19											
	Virupakshanagar 5th cross road.											
	0.00	15.00		1.00	15.00	6.80	5.90	6.35	0.20	19.05		
	15.00	30.00		1.00	15.00	5.90	5.90	5.90	0.20	17.70		
	30.00	45.00		1.00	15.00	5.90	5.80	6.00	0.20	18.00		
	45.00	60.00		1.00	15.00	6.30	5.80	6.05	0.20	18.15		
	60.00	75.00		1.00	15.00	5.80	5.40	5.60	0.20	16.80		
	75.00	90.00		1.00	15.00	5.40	5.40	6.00	0.20	18.00		
	90.00	105.00		1.00	15.00	5.40	5.70	5.55	0.20	16.65		
	105.00	120.00		1.00	15.00	5.70	5.70	5.70	0.20	17.10		
	120.00	135.00		1.00	15.00	5.70	5.60	5.65	0.20	16.95		
	135.00	150.00		1.00	15.00	5.60	5.60	5.60	0.20	16.80		
	150.00	165.00		1.00	15.00	5.60	4.90	5.25	0.20	15.75		
	165.00	180.00		1.00	15.00	4.90	4.90	4.90	0.20	14.70		
	180.00	195.00		1.00	15.00	4.90	5.20	5.05	0.20	15.15		
	195.00	210.00		1.00	15.00	5.20	5.20	5.20	0.20	15.60		
	210.00	214.00		1.00	4.00	5.20	5.30	5.25	0.20	4.20		
	Virupakshanagar 4th cross road.											
	0.00	15.00		1.00	15.00	6.10	6.30	6.20	0.20	18.60		
	15.00	30.00		1.00	15.00	6.30	6.30	6.30	0.20	18.90		
	30.00	45.00		1.00	15.00	6.30	5.90	6.00	0.20	18.00		
	45.00	60.00		1.00	15.00	6.30	5.90	6.10	0.20	18.30		
	60.00	75.00		1.00	15.00	5.90	5.30	5.60	0.20	16.80		
	75.00	90.00		1.00	15.00	5.30	5.30	6.00	0.20	18.00		
	90.00	105.00		1.00	15.00	5.30	4.60	4.95	0.20	14.85		
	105.00	120.00		1.00	15.00	4.60	4.60	4.60	0.20	13.80		
	120.00	135.00		1.00	15.00	4.60	4.30	4.45	0.20	13.35		
	135.00	150.00		1.00	15.00	4.30	4.30	4.30	0.20	12.90		
	150.00	165.00		1.00	15.00	4.30	4.40	4.35	0.20	13.05		
	165.00	180.00		1.00	15.00	4.40	4.40	4.40	0.20	13.20		
	180.00	195.00		1.00	15.00	4.40	4.60	4.50	0.20	13.50		
	195.00	208.00		1.00	13.00	4.60	4.60	4.60	0.20	11.96		
	Virupakshanagar 3rd cross road.											
	0.00	15.00		1.00	15.00	8.10	6.40	7.25	0.20	21.75		
	15.00	30.00		1.00	15.00	6.40	6.40	6.40	0.20	19.20		
	30.00	45.00		1.00	15.00	6.40	5.60	6.00	0.20	18.00		
	45.00	60.00		1.00	15.00	6.30	5.60	5.95	0.20	17.85		
	60.00	75.00		1.00	15.00	5.60	5.20	5.40	0.20	16.20		
	75.00	90.00		1.00	15.00	5.20	5.20	6.00	0.20	18.00		
	90.00	105.00		1.00	15.00	5.20	5.90	5.55	0.20	16.65		
	105.00	120.00		1.00	15.00	5.90	5.90	5.90	0.20	17.70		
	120.00	135.00		1.00	15.00	5.90	5.50	5.70	0.20	17.10		
	135.00	150.00		1.00	15.00	5.50	5.50	5.50	0.20	16.50		
	150.00	165.00		1.00	15.00	5.50	5.20	5.35	0.20	16.05		
	165.00	180.00		1.00	15.00	5.20	5.20	5.20	0.20	15.60		
	180.00	195.00		1.00	15.00	5.20	8.20	6.70	0.20	20.10		
	195.00	210.00		1.00	15.00	8.20	8.20	8.20	0.20	24.60		
	210.00	225.00		1.00	15.00	8.20	6.20	7.20	0.20	21.60		
	225.00	240.00		1.00	15.00	6.20	6.20	6.20	0.20	18.60		
	240.00	255.00		1.00	15.00	6.20	6.30	6.25	0.20	18.75		
	255.00	270.00		1.00	15.00	6.30	6.30	6.30	0.20	18.90		
	270.00	285.00		1.00	15.00	6.30	7.50	6.90	0.20	20.70		
	285.00	300.00		1.00	15.00	7.50	7.50	7.50	0.20	22.50		
	300.00	308.00		1.00	8.00	7.50	7.50	7.50	0.20	12.00		
	308.00	310.00		0.00	0.00	0.00	0.00	0.00	0.20	0.00		
	310.00	325.00		1.00	15.00	0.00	7.30	3.65	0.20	10.95		
	325.00	330.00		1.00	5.00	7.30	7.30	7.30	0.20	7.30		

Q Item No	Description / Chainage		Side	Nos	Length	Width B1	Width B2	Width Avg B	Depth	Quantity	Unit/ Remarks	Rate	Amount
3rd C cross Road Yarappa Garden													
	0.00	0.00		1.00	14.00	4.90	4.50	4.70	0.20	13.16			
2nd Cross Road Gas Godown Road													
				1.00	8.00	2.50	2.50	2.50	0.20	4.00			
				1.00	12.00	1.20	1.20	1.20	0.20	2.88			
				1.00	5.00	1.20	1.20	1.20	0.20	1.20			
				1.00	11.00	2.50	2.50	2.50	0.20	5.50			
				1.00	6.00	0.90	0.90	0.90	0.20	1.08			
Edge Restoration													
Telicom Layout 4th Cross Road													
LHS													
	0.00	13.50		1.00	13.50	0.80	1.00	0.90	0.20	2.43			
	13.50	15.00		1.00	1.50	0.80	1.00	0.90	0.20	0.27			
	15.00	16.00		1.00	1.00	0.75	0.90	0.83	0.20	0.17			
	16.00	30.00		1.00	14.00	0.90	1.00	0.95	0.20	2.66			
	30.00	45.00		1.00	15.00	0.75	1.00	0.88	0.20	2.63			
	45.00	59.00		1.00	14.00	0.90	0.80	1.00	0.20	2.80			
	59.00	60.00		1.00	1.00	0.80	0.60	0.70	0.20	0.14			
	60.00	63.00		1.00	3.00	0.60	0.60	0.60	0.20	0.36			
	63.00	75.00		1.00	12.00	0.60	0.75	0.68	0.20	1.62			
	75.00	78.00		1.00	3.00	0.60	1.00	0.80	0.20	0.48			
	110.00	115.00		1.00	5.00	0.80	1.00	0.90	0.20	0.90			
	115.00	125.00		1.00	10.00	0.80	1.00	0.90	0.20	1.80			
	151.50	160.00		1.00	8.50	1.50	1.50	1.50	0.20	2.55			
	160.00	171.50		1.00	11.50	0.60	1.00	0.80	0.20	1.84			
Telicom Layout 4th Cross Road													
RHS													
	0.00	13.50		1.00	13.50	0.90	0.75	0.83	0.20	2.23			
	16.00	30.00		1.00	14.00	0.90	0.90	0.90	0.20	2.52			
	30.00	45.00		1.00	15.00	0.60	0.90	0.75	0.20	2.25			
	45.00	59.00		1.00	14.00	0.75	0.90	0.83	0.20	2.31			
	63.00	75.00		1.00	12.00	0.75	0.80	0.78	0.20	1.86			
	75.00	78.00		1.00	3.00	0.80	0.90	0.85	0.20	0.51			
	78.00	85.00		1.00	7.00	0.80	1.00	0.90	0.20	1.26			
	98.00	105.00		1.00	7.00	0.90	1.00	0.95	0.20	1.33			
	105.00	110.00		1.00	5.00	0.80	1.00	0.90	0.20	0.90			
	110.00	115.00		1.00	5.00	0.90	1.00	0.95	0.20	0.95			
	125.00	133.00		1.00	8.00	0.80	1.00	0.90	0.20	1.44			
2nd Main Road Telicom Layout													
LHS													
	78.00	90.00		1.00	12.00	1.00	0.90	0.95	0.20	2.28			
	90.00	91.00		1.00	1.00	1.00	1.00	1.00	0.20	0.20			
	91.00	105.00		1.00	14.00	1.00	1.00	1.00	0.20	2.80			
	105.00	109.00		1.00	4.00	1.00	1.00	1.00	0.20	0.80			
	126.00	135.00		1.00	9.00	1.00	1.00	1.00	0.20	1.80			
	135.00	143.50		1.00	8.50	0.90	1.00	0.95	0.20	1.62			
	143.50	150.00		1.00	6.50	0.90	0.90	0.90	0.20	1.17			
	150.00	165.00		1.00	15.00	0.90	0.90	0.90	0.20	2.70			
	165.00	180.00		1.00	15.00	0.90	0.90	0.90	0.20	2.70			
	180.00	185.00		1.00	5.00	1.00	1.00	1.00	0.20	1.00			
	185.00	195.00		1.00	10.00	1.00	1.00	1.00	0.20	2.00			
	195.00	208.00		1.00	13.00	1.00	1.00	1.00	0.20	2.60			
	208.00	210.00		1.00	2.00	1.00	1.00	1.00	0.20	0.40			
	210.00	220.00		1.00	10.00	1.00	1.00	1.00	0.20	2.00			
	220.00	225.00		1.00	5.00	1.00	1.00	1.00	0.20	1.00			
	225.00	240.00		1.00	15.00	1.00	1.00	1.00	0.20	3.00			
	240.00	245.00		1.00	5.00	1.00	1.00	1.00	0.20	1.00			
	253.00	255.00		1.00	2.00	0.90	0.90	0.90	0.20	0.36			
	255.00	270.00		1.00	15.00	0.90	0.90	0.90	0.20	2.70			
	270.00	285.00		1.00	15.00	0.90	0.90	0.90	0.20	2.70			
	285.00	300.00		1.00	15.00	0.90	0.90	0.90	0.20	2.70			
	300.00	315.00		1.00	15.00	1.00	1.00	1.00	0.20	3.00			
	315.00	330.00		1.00	15.00	1.00	1.00	1.00	0.20	3.00			
	330.00	345.00		1.00	15.00	1.00	1.00	1.00	0.20	3.00			

BOQ Item No	Description		Side	Nos	Length	Width			Depth	Quantity	Unit/ Remarks	Rate	
	Chainage					B1	B2	Avg B					
	345.00	360.00		1.00	15.00	1.00	1.00	1.00	0.20	3.00			
	360.00	375.00		1.00	15.00	1.00	1.00	1.00	0.20	3.00			
	375.00	390.00		1.00	15.00	1.00	1.00	1.00	0.20	3.00			
	390.00	405.00		1.00	15.00	1.00	1.00	1.00	0.20	3.00			
	405.00	417.00		1.00	12.00	0.80	0.90	0.85	0.20	2.04			
	2nd Main Road Telicom Layout												
	RHS												
	78.00	90.00		1.00	12.00	1.00	1.20	1.10	0.20	2.64			
	90.00	91.00		1.00	1.00	0.80	0.75	0.78	0.20	0.16			
	143.50	150.00		1.00	6.50	0.80	0.60	0.70	0.20	0.91			
	150.00	165.00		1.00	15.00	0.60	1.20	0.90	0.20	2.70			
	165.00	180.00		1.00	15.00	0.60	1.00	0.80	0.20	2.40			
	180.00	185.00		1.00	5.00	0.60	1.00	0.80	0.20	0.80			
	240.00	245.00		1.00	5.00	0.60	1.20	0.90	0.20	0.90			
	245.00	250.00		1.00	5.00	0.60	1.00	0.80	0.20	0.80			
	UGD Restoration												
	Ganesh Nagar Road												
	0.00	15.00		1.00	15.00	1.20	1.20	1.20	0.20	3.60			
	15.00	30.00		1.00	15.00	1.20	1.20	1.20	0.20	3.60			
	30.00	45.00		1.00	15.00	1.20	1.20	1.20	0.20	3.60			
	45.00	60.00		1.00	15.00	1.20	1.20	1.20	0.20	3.60			
	60.00	75.00		1.00	15.00	1.20	1.20	1.20	0.20	3.60			
	75.00	90.00		1.00	15.00	1.20	1.20	1.20	0.20	3.60			
	90.00	105.00		1.00	15.00	1.20	1.20	1.20	0.20	3.60			
	105.00	120.00		1.00	15.00	1.20	1.20	1.20	0.20	3.60			
	120.00	135.00		1.00	15.00	1.20	1.20	1.20	0.20	3.60			
	135.00	150.00		1.00	15.00	1.20	1.20	1.20	0.20	3.60			
	150.00	165.00		1.00	15.00	1.20	1.20	1.20	0.20	3.60			
	165.00	180.00		1.00	15.00	1.20	1.20	1.20	0.20	3.60			
	180.00	195.00		1.00	15.00	1.20	1.20	1.20	0.20	3.60			
	195.00	210.00		1.00	15.00	1.20	1.20	1.20	0.20	3.60			
	210.00	225.00		1.00	15.00	1.20	1.20	1.20	0.20	3.60			
	225.00	240.00		1.00	15.00	1.20	1.20	1.20	0.20	3.60			
	240.00	255.00		1.00	15.00	1.20	1.20	1.20	0.20	3.60			
	255.00	270.00		1.00	15.00	1.20	1.20	1.20	0.20	3.60			
	270.00	285.00		1.00	15.00	1.20	1.20	1.20	0.20	3.60			
	285.00	300.00		1.00	15.00	1.20	1.20	1.20	0.20	3.60			
	300.00	315.00		1.00	15.00	1.20	1.20	1.20	0.20	3.60			
	315.00	330.00		1.00	15.00	1.20	1.20	1.20	0.20	3.60			
	330.00	338.50		1.00	8.50	1.20	1.20	1.20	0.20	2.04			
								Total Quantity		**1081.54**			
									BOQ	**740.62**			
								Qty Upto 125%		**925.78**	**Cum**	**1919.11**	177667
								Qty Above 125%		**155.76**	**Cum**	**2014.87**	31383
3	KSRRB M400-17. Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No. 406 Page No. 155/ Item No. 20.18/ PWD SR 2018-19												
	Virupakshanagar 5th cross road.												
	0.00	15.00		1	15.00	6.80	5.90	6.35	0.23	21.91			
	15.00	30.00		1	15.00	5.90	5.90	5.90	0.23	20.36			
	30.00	45.00		1	15.00	5.90	5.80	6.00	0.23	20.70			
	45.00	60.00		1	15.00	6.30	5.80	6.05	0.23	20.87			
	60.00	75.00		1	15.00	5.80	5.40	5.60	0.23	19.32			
	75.00	90.00		1	15.00	5.40	5.40	6.00	0.23	20.70			
	90.00	105.00		1	15.00	5.40	5.70	5.55	0.23	19.15			
	105.00	120.00		1	15.00	5.70	5.70	5.70	0.23	19.67			
	120.00	135.00		1	15.00	5.70	5.60	5.65	0.23	19.49			
	135.00	150.00		1	15.00	5.60	5.60	5.60	0.23	19.32			

OQ Item No	Description Chainage		Side	Nos	Length	Width B1	Width B2	Width Avg B	Depth	Quantity	Unit/ Remarks	Rate	Amount
	150.00	165.00		1	15.00	5.60	4.90	5.25	0.23	18.11			
	165.00	180.00		1	15.00	4.90	4.90	4.90	0.23	16.91			
	180.00	195.00		1	15.00	4.90	5.20	5.05	0.23	17.42			
	195.00	210.00		1	15.00	5.20	5.20	5.20	0.23	17.94			
	210.00	214.00		1	4.00	5.20	5.30	5.25	0.23	4.83			
	Virupakshanagar 4th cross road.												
	0.00	15.00		1	15.00	6.10	6.30	6.20	0.23	21.39			
	15.00	30.00		1	15.00	6.30	6.30	6.30	0.23	21.74			
	30.00	45.00		1	15.00	6.30	5.90	6.00	0.23	20.70			
	45.00	60.00		1	15.00	6.30	5.90	6.10	0.23	21.05			
	60.00	75.00		1	15.00	5.90	5.30	5.60	0.23	19.32			
	75.00	90.00		1	15.00	5.30	5.30	6.00	0.23	20.70			
	90.00	105.00		1	15.00	5.30	4.60	4.95	0.23	17.08			
	105.00	120.00		1	15.00	4.60	4.60	4.60	0.23	15.87			
	120.00	135.00		1	15.00	4.60	4.30	4.45	0.23	15.35			
	135.00	150.00		1	15.00	4.30	4.30	4.30	0.23	14.84			
	150.00	165.00		1	15.00	4.30	4.40	4.35	0.23	15.01			
	165.00	180.00		1	15.00	4.40	4.40	4.40	0.23	15.18			
	180.00	195.00		1	15.00	4.40	4.60	4.50	0.23	15.53			
	195.00	208.00		1	13.00	4.60	4.60	4.60	0.23	13.75			
	Virupakshanagar 3rd cross road.												
	0.00	15.00		1	15.00	8.10	6.40	7.25	0.23	25.01			
	15.00	30.00		1	15.00	6.40	6.40	6.40	0.23	22.08			
	30.00	45.00		1	15.00	6.40	5.60	6.00	0.23	20.70			
	45.00	60.00		1	15.00	6.30	5.60	5.95	0.23	20.53			
	60.00	75.00		1	15.00	5.60	5.20	5.40	0.23	18.63			
	75.00	90.00		1	15.00	5.20	5.20	6.00	0.23	20.70			
	90.00	105.00		1	15.00	5.20	5.90	5.55	0.23	19.15			
	105.00	120.00		1	15.00	5.90	5.90	5.90	0.23	20.36			
	120.00	135.00		1	15.00	5.90	5.50	5.70	0.23	19.67			
	135.00	150.00		1	15.00	5.50	5.50	5.50	0.23	18.98			
	150.00	165.00		1	15.00	5.50	5.20	5.35	0.23	18.46			
	165.00	180.00		1	15.00	5.20	5.20	5.20	0.23	17.94			
	180.00	195.00		1	15.00	5.20	8.20	6.70	0.23	23.12			
	195.00	210.00		1	15.00	8.20	8.20	8.20	0.23	28.29			
	210.00	225.00		1	15.00	8.20	6.20	7.20	0.23	24.84			
	225.00	240.00		1	15.00	6.20	6.20	6.20	0.23	21.39			
	240.00	255.00		1	15.00	6.20	6.30	6.25	0.23	21.56			
	255.00	270.00		1	15.00	6.30	6.30	6.30	0.23	21.74			
	270.00	285.00		1	15.00	6.30	7.50	6.90	0.23	23.81			
	285.00	300.00		1	15.00	7.50	7.50	7.50	0.23	25.88			
	300.00	308.00		1	8.00	7.50	7.50	7.50	0.23	13.80			
	308.00	310.00		0	0.00	0.00	0.00	0.00	0.23	0.00			
	310.00	325.00		1	15.00	0.00	7.30	3.65	0.23	12.59			
	325.00	330.00		1	5.00	7.30	7.30	7.30	0.23	8.40			
	3rd C cross Road Yarappa Garden												
	0.00	0.00		1	14.00	4.90	4.50	4.70	0.15	9.87			
	2nd Cross Road Gas Godown Road												
				1.00	8.00	2.50	2.50	2.50	0.15	3.00			
				1.00	12.00	1.20	1.20	1.20	0.15	2.16			
				1.00	5.00	1.20	1.20	1.20	0.15	0.90			
				1.00	11.00	2.50	2.50	2.50	0.15	4.13			
				1.00	6.00	0.90	0.90	0.90	0.15	0.81			
	Edge Restoration												
	Telicom Layout 4th Cross Road												
	LHS												
	0.00	13.50		1	13.50	0.80	1.00	0.90	0.15	1.82			
	13.50	15.00		1	1.50	0.80	1.00	0.90	0.15	0.20			
	15.00	16.00		1	1.00	0.75	0.90	0.83	0.15	0.12			
	16.00	30.00		1	14.00	0.90	1.00	0.95	0.15	2.00			
	30.00	45.00		1	15.00	0.75	1.00	0.88	0.15	1.97			
	45.00	59.00		1	14.00	0.90	0.80	1.00	0.15	2.10			

BOQ Item No	Description Chainage		Side	Nos	Length	Width B1	Width B2	Width Avg B	Depth	Quantity	Unit/ Remarks	Rate
	59.00	60.00		1	1.00	0.80	0.60	0.70	0.15	0.11		
	60.00	63.00		1	3.00	0.60	0.60	0.60	0.15	0.27		
	63.00	75.00		1	12.00	0.60	0.75	0.68	0.15	1.22		
	75.00	78.00		1	3.00	0.60	1.00	0.80	0.15	0.36		
	110.00	115.00		1	5.00	0.80	1.00	0.90	0.15	0.68		
	115.00	125.00		1	10.00	0.80	1.00	0.90	0.15	1.35		
	151.50	160.00		1	8.50	1.50	1.50	1.50	0.15	1.91		
	160.00	171.50		1	11.50	0.60	1.00	0.80	0.15	1.38		
	Telicom Layout 4th Cross Road											
	RHS											
	0.00	13.50		1	13.50	0.90	0.75	0.83	0.15	1.67		
	16.00	30.00		1	14.00	0.90	0.90	0.90	0.15	1.89		
	30.00	45.00		1	15.00	0.60	0.90	0.75	0.15	1.69		
	45.00	59.00		1	14.00	0.75	0.90	0.83	0.15	1.73		
	63.00	75.00		1	12.00	0.75	0.80	0.78	0.15	1.40		
	75.00	78.00		1	3.00	0.80	0.90	0.85	0.15	0.38		
	78.00	85.00		1	7.00	0.80	1.00	0.90	0.15	0.95		
	98.00	105.00		1	7.00	0.90	1.00	0.95	0.15	1.00		
	105.00	110.00		1	5.00	0.80	1.00	0.90	0.15	0.68		
	110.00	115.00		1	5.00	0.90	1.00	0.95	0.15	0.71		
	125.00	133.00		1	8.00	0.80	1.00	0.90	0.15	1.08		
	2nd Main Road Telicom Layout											
	LHS											
	78.00	90.00		1	12.00	1.00	0.90	0.95	0.15	1.71		
	90.00	91.00		1	1.00	1.00	1.00	1.00	0.15	0.15		
	91.00	105.00		1	14.00	1.00	1.00	1.00	0.15	2.10		
	105.00	109.00		1	4.00	1.00	1.00	1.00	0.15	0.60		
	126.00	135.00		1	9.00	1.00	1.00	1.00	0.15	1.35		
	135.00	143.50		1	8.50	0.90	1.00	0.95	0.15	1.21		
	143.50	150.00		1	6.50	0.90	0.90	0.90	0.15	0.88		
	150.00	165.00		1	15.00	0.90	0.90	0.90	0.15	2.03		
	165.00	180.00		1	15.00	0.90	0.90	0.90	0.15	2.03		
	180.00	185.00		1	5.00	1.00	1.00	1.00	0.15	0.75		
	185.00	195.00		1	10.00	1.00	1.00	1.00	0.15	1.50		
	195.00	208.00		1	13.00	1.00	1.00	1.00	0.15	1.95		
	208.00	210.00		1	2.00	1.00	1.00	1.00	0.15	0.30		
	210.00	220.00		1	10.00	1.00	1.00	1.00	0.15	1.50		
	220.00	225.00		1	5.00	1.00	1.00	1.00	0.15	0.75		
	225.00	240.00		1	15.00	1.00	1.00	1.00	0.15	2.25		
	240.00	245.00		1	5.00	1.00	1.00	1.00	0.15	0.75		
	253.00	255.00		1	2.00	0.90	0.90	0.90	0.15	0.27		
	255.00	270.00		1	15.00	0.90	0.90	0.90	0.15	2.03		
	270.00	285.00		1	15.00	0.90	0.90	0.90	0.15	2.03		
	285.00	300.00		1	15.00	0.90	0.90	0.90	0.15	2.03		
	300.00	315.00		1	15.00	1.00	1.00	1.00	0.15	2.25		
	315.00	330.00		1	15.00	1.00	1.00	1.00	0.15	2.25		
	330.00	345.00		1	15.00	1.00	1.00	1.00	0.15	2.25		
	345.00	360.00		1	15.00	1.00	1.00	1.00	0.15	2.25		
	360.00	375.00		1	15.00	1.00	1.00	1.00	0.15	2.25		
	375.00	390.00		1	15.00	1.00	1.00	1.00	0.15	2.25		
	390.00	405.00		1	15.00	1.00	1.00	1.00	0.15	2.25		
	405.00	417.00		1	12.00	0.80	0.90	0.85	0.15	1.53		
	2nd Main Road Telicom Layout											
	RHS											
	78.00	90.00		1	12.00	1.00	1.20	1.10	0.15	1.98		
	90.00	91.00		1	1.00	0.80	0.75	0.78	0.15	0.12		
	143.50	150.00		1	6.50	0.80	0.60	0.70	0.15	0.68		
	150.00	165.00		1	15.00	0.60	1.20	0.90	0.15	2.03		
	165.00	180.00		1	15.00	0.60	1.00	0.80	0.15	1.80		
	180.00	185.00		1	5.00	0.60	1.00	0.80	0.15	0.60		
	240.00	245.00		1	5.00	0.60	1.20	0.90	0.15	0.68		
	245.00	250.00		1	5.00	0.60	1.00	0.80	0.15	0.60		

DQ Item No	Description / Chainage		Side	Nos	Length	Width B1	Width B2	Width Avg B	Depth	Quantity	Unit/ Remarks	Rate	Amount
	UGD Restoration												
	Ganesh Nagar Road												
	0.00	15.00		1	15.00	1.20	1.20	1.20	0.15	2.70			
	15.00	30.00		1	15.00	1.20	1.20	1.20	0.15	2.70			
	30.00	45.00		1	15.00	1.20	1.20	1.20	0.15	2.70			
	45.00	60.00		1	15.00	1.20	1.20	1.20	0.15	2.70			
	60.00	75.00		1	15.00	1.20	1.20	1.20	0.15	2.70			
	75.00	90.00		1	15.00	1.20	1.20	1.20	0.15	2.70			
	90.00	105.00		1	15.00	1.20	1.20	1.20	0.15	2.70			
	105.00	120.00		1	15.00	1.20	1.20	1.20	0.15	2.70			
	120.00	135.00		1	15.00	1.20	1.20	1.20	0.15	2.70			
	135.00	150.00		1	15.00	1.20	1.20	1.20	0.15	2.70			
	150.00	165.00		1	15.00	1.20	1.20	1.20	0.15	2.70			
	165.00	180.00		1	15.00	1.20	1.20	1.20	0.15	2.70			
	180.00	195.00		1	15.00	1.20	1.20	1.20	0.15	2.70			
	195.00	210.00		1	15.00	1.20	1.20	1.20	0.15	2.70			
	210.00	225.00		1	15.00	1.20	1.20	1.20	0.15	2.70			
	225.00	240.00		1	15.00	1.20	1.20	1.20	0.15	2.70			
	240.00	255.00		1	15.00	1.20	1.20	1.20	0.15	2.70			
	255.00	270.00		1	15.00	1.20	1.20	1.20	0.15	2.70			
	270.00	285.00		1	15.00	1.20	1.20	1.20	0.15	2.70			
	285.00	300.00		1	15.00	1.20	1.20	1.20	0.15	2.70			
	300.00	315.00		1	15.00	1.20	1.20	1.20	0.15	2.70			
	315.00	330.00		1	15.00	1.20	1.20	1.20	0.15	2.70			
	330.00	338.50		1	8.50	1.20	1.20	1.20	0.15	1.53			
								Total Quantity		**1156.120**	**Cum**	**1925.23**	**2225796.91**
4	KSRRB M500-6. Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WMM ,including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per Specifications. MORTH Specification No. 502 Complete with all lead and lift and as per the direction of the Engineer-in-Charge. Page No. 158/ Item No. 21.6/ PWD SR 2018-19 Issue Rates												
	Virupakshanagar 5th cross road.												
	0.00	15.00		1	15.00	6.80	5.90	6.35		95.25			
	15.00	30.00		1	15.00	5.90	5.90	5.90		88.50			
	30.00	45.00		1	15.00	5.90	5.80	6.00		90.00			
	45.00	60.00		1	15.00	6.30	5.80	6.05		90.75			
	60.00	75.00		1	15.00	5.80	5.40	5.60		84.00			
	75.00	90.00		1	15.00	5.40	5.40	6.00		90.00			
	90.00	105.00		1	15.00	5.40	5.70	5.55		83.25			
	105.00	120.00		1	15.00	5.70	5.70	5.70		85.50			
	120.00	135.00		1	15.00	5.70	5.60	5.65		84.75			
	135.00	150.00		1	15.00	5.60	5.60	5.60		84.00			
	150.00	165.00		1	15.00	5.60	4.90	5.25		78.75			
	165.00	180.00		1	15.00	4.90	4.90	4.90		73.50			
	180.00	195.00		1	15.00	4.90	5.20	5.05		75.75			
	195.00	210.00		1	15.00	5.20	5.20	5.20		78.00			
	210.00	214.00		1	4.00	5.20	5.30	5.25		21.00			
	Virupakshanagar 4th cross road.												
	0.00	15.00		1	15.00	6.10	6.30	6.20		93.00			
	15.00	30.00		1	15.00	6.30	6.30	6.30		94.50			
	30.00	45.00		1	15.00	6.30	5.90	6.00		90.00			
	45.00	60.00		1	15.00	6.30	5.90	6.10		91.50			
	60.00	75.00		1	15.00	5.90	5.30	5.60		84.00			
	75.00	90.00		1	15.00	5.30	5.30	6.00		90.00			
	90.00	105.00		1	15.00	5.30	4.60	4.95		74.25			
	105.00	120.00		1	15.00	4.60	4.60	4.60		69.00			
	120.00	135.00		1	15.00	4.60	4.30	4.45		66.75			
	135.00	150.00		1	15.00	4.30	4.30	4.30		64.50			
	150.00	165.00		1	15.00	4.30	4.40	4.35		65.25			
	165.00	180.00		1	15.00	4.40	4.40	4.40		66.00			

BOQ Item No	Description		Side	Nos	Length	Width			Depth	Quantity	Unit/ Remarks	Rate
	Chainage					B1	B2	Avg B				
	180.00	195.00		1	15.00	4.40	4.60	4.50		67.50		
	195.00	208.00		1	13.00	4.60	4.60	4.60		59.80		
	Virupakshanagar 3rd cross road.											
	0.00	15.00		1	15.00	8.10	6.40	7.25		108.75		
	15.00	30.00		1	15.00	6.40	6.40	6.40		96.00		
	30.00	45.00		1	15.00	6.40	5.60	6.00		90.00		
	45.00	60.00		1	15.00	6.30	5.60	5.95		89.25		
	60.00	75.00		1	15.00	5.60	5.20	5.40		81.00		
	75.00	90.00		1	15.00	5.20	5.20	6.00		90.00		
	90.00	105.00		1	15.00	5.20	5.90	5.55		83.25		
	105.00	120.00		1	15.00	5.90	5.90	5.90		88.50		
	120.00	135.00		1	15.00	5.90	5.50	5.70		85.50		
	135.00	150.00		1	15.00	5.50	5.50	5.50		82.50		
	150.00	165.00		1	15.00	5.50	5.20	5.35		80.25		
	165.00	180.00		1	15.00	5.20	5.20	5.20		78.00		
	180.00	195.00		1	15.00	5.20	8.20	6.70		100.50		
	195.00	210.00		1	15.00	8.20	8.20	8.20		123.00		
	210.00	225.00		1	15.00	8.20	6.20	7.20		108.00		
	225.00	240.00		1	15.00	6.20	6.20	6.20		93.00		
	240.00	255.00		1	15.00	6.20	6.30	6.25		93.75		
	255.00	270.00		1	15.00	6.30	6.30	6.30		94.50		
	270.00	285.00		1	15.00	6.30	7.50	6.90		103.50		
	285.00	300.00		1	15.00	7.50	7.50	7.50		112.50		
	300.00	308.00		1	8.00	7.50	7.50	7.50		60.00		
	308.00	310.00		0	0.00	0.00	0.00	0.00		0.00		
	310.00	325.00		1	15.00	0.00	7.30	3.65		54.75		
	325.00	330.00		1	5.00	7.30	7.30	7.30		36.50		
	3rd C cross Road Yarappa Garden											
	0.00	0.00		1	14.00	4.90	4.50	4.70		65.80		
	2nd Cross Road Gas Godown Road											
				1.00	8.00	2.50	2.50	2.50		20.00		
				1.00	12.00	1.20	1.20	1.20		14.40		
				1.00	5.00	1.20	1.20	1.20		6.00		
				1.00	11.00	2.50	2.50	2.50		27.50		
				1.00	6.00	0.90	0.90	0.90		5.40		
	Edge Restoration											
	Telicom Layout 4th Cross Road											
	LHS											
	0.00	13.50		1	13.50	0.80	1.00	0.90		12.15		
	13.50	15.00		1	1.50	0.80	1.00	0.90		1.35		
	15.00	16.00		1	1.00	0.75	0.90	0.83		0.83		
	16.00	30.00		1	14.00	0.90	1.00	0.95		13.30		
	30.00	45.00		1	15.00	0.75	1.00	0.88		13.13		
	45.00	59.00		1	14.00	0.90	0.80	1.00		14.00		
	59.00	60.00		1	1.00	0.80	0.60	0.70		0.70		
	60.00	63.00		1	3.00	0.60	0.60	0.60		1.80		
	63.00	75.00		1	12.00	0.60	0.75	0.68		8.10		
	75.00	78.00		1	3.00	0.60	1.00	0.80		2.40		
	110.00	115.00		1	5.00	0.80	1.00	0.90		4.50		
	115.00	125.00		1	10.00	0.80	1.00	0.90		9.00		
	151.50	160.00		1	8.50	1.50	1.50	1.50		12.75		
	160.00	171.50		1	11.50	0.60	1.00	0.80		9.20		
	Telicom Layout 4th Cross Road											
	RHS											
	0.00	13.50		1	13.50	0.90	0.75	0.83		11.14		
	16.00	30.00		1	14.00	0.90	0.90	0.90		12.60		
	30.00	45.00		1	15.00	0.60	0.90	0.75		11.25		
	45.00	59.00		1	14.00	0.75	0.90	0.83		11.55		
	63.00	75.00		1	12.00	0.75	0.80	0.78		9.30		
	75.00	78.00		1	3.00	0.80	0.90	0.85		2.55		
	78.00	85.00		1	7.00	0.80	1.00	0.90		6.30		
	98.00	105.00		1	7.00	0.90	1.00	0.95		6.65		
	105.00	110.00		1	5.00	0.80	1.00	0.90		4.50		

Description		Side	Nos	Length	Width			Depth	Quantity	Unit/ Remarks	Rate	Amount
Chainage					B1	B2	Avg B					
110.00	115.00		1	5.00	0.90	1.00	0.95		4.75			
125.00	133.00		1	8.00	0.80	1.00	0.90		7.20			
2nd Main Road Telicom Layout												
LHS												
78.00	90.00		1	12.00	1.00	0.90	0.95		11.40			
90.00	91.00		1	1.00	1.00	1.00	1.00		1.00			
91.00	105.00		1	14.00	1.00	1.00	1.00		14.00			
105.00	109.00		1	4.00	1.00	1.00	1.00		4.00			
126.00	135.00		1	9.00	1.00	1.00	1.00		9.00			
135.00	143.50		1	8.50	0.90	1.00	0.95		8.08			
143.50	150.00		1	6.50	0.90	0.90	0.90		5.85			
150.00	165.00		1	15.00	0.90	0.90	0.90		13.50			
165.00	180.00		1	15.00	0.90	0.90	0.90		13.50			
180.00	185.00		1	5.00	1.00	1.00	1.00		5.00			
185.00	195.00		1	10.00	1.00	1.00	1.00		10.00			
195.00	208.00		1	13.00	1.00	1.00	1.00		13.00			
208.00	210.00		1	2.00	1.00	1.00	1.00		2.00			
210.00	220.00		1	10.00	1.00	1.00	1.00		10.00			
220.00	225.00		1	5.00	1.00	1.00	1.00		5.00			
225.00	240.00		1	15.00	1.00	1.00	1.00		15.00			
240.00	245.00		1	5.00	1.00	1.00	1.00		5.00			
253.00	255.00		1	2.00	0.90	0.90	0.90		1.80			
255.00	270.00		1	15.00	0.90	0.90	0.90		13.50			
270.00	285.00		1	15.00	0.90	0.90	0.90		13.50			
285.00	300.00		1	15.00	0.90	0.90	0.90		13.50			
300.00	315.00		1	15.00	1.00	1.00	1.00		15.00			
315.00	330.00		1	15.00	1.00	1.00	1.00		15.00			
330.00	345.00		1	15.00	1.00	1.00	1.00		15.00			
345.00	360.00		1	15.00	1.00	1.00	1.00		15.00			
360.00	375.00		1	15.00	1.00	1.00	1.00		15.00			
375.00	390.00		1	15.00	1.00	1.00	1.00		15.00			
390.00	405.00		1	15.00	1.00	1.00	1.00		15.00			
405.00	417.00		1	12.00	0.80	0.90	0.85		10.20			
2nd Main Road Telicom Layout												
RHS												
78.00	90.00		1	12.00	1.00	1.20	1.10		13.20			
90.00	91.00		1	1.00	0.80	0.75	0.78		0.78			
143.50	150.00		1	6.50	0.80	0.60	0.70		4.55			
150.00	165.00		1	15.00	0.60	1.20	0.90		13.50			
165.00	180.00		1	15.00	0.60	1.00	0.80		12.00			
180.00	185.00		1	5.00	0.60	1.00	0.80		4.00			
240.00	245.00		1	5.00	0.60	1.20	0.90		4.50			
245.00	250.00		1	5.00	0.60	1.00	0.80		4.00			
UGD Restoration												
Ganesh Nagar Road												
0.00	15.00		1	15.00	1.20	1.20	1.20		18.00			
15.00	30.00		1	15.00	1.20	1.20	1.20		18.00			
30.00	45.00		1	15.00	1.20	1.20	1.20		18.00			
45.00	60.00		1	15.00	1.20	1.20	1.20		18.00			
60.00	75.00		1	15.00	1.20	1.20	1.20		18.00			
75.00	90.00		1	15.00	1.20	1.20	1.20		18.00			
90.00	105.00		1	15.00	1.20	1.20	1.20		18.00			
105.00	120.00		1	15.00	1.20	1.20	1.20		18.00			
120.00	135.00		1	15.00	1.20	1.20	1.20		18.00			
135.00	150.00		1	15.00	1.20	1.20	1.20		18.00			
150.00	165.00		1	15.00	1.20	1.20	1.20		18.00			
165.00	180.00		1	15.00	1.20	1.20	1.20		18.00			
180.00	195.00		1	15.00	1.20	1.20	1.20		18.00			
195.00	210.00		1	15.00	1.20	1.20	1.20		18.00			
210.00	225.00		1	15.00	1.20	1.20	1.20		18.00			
225.00	240.00		1	15.00	1.20	1.20	1.20		18.00			
240.00	255.00		1	15.00	1.20	1.20	1.20		18.00			
255.00	270.00		1	15.00	1.20	1.20	1.20		18.00			

BOQ Item No	Description Chainage		Side	Nos	Length	Width B1	Width B2	Width Avg B	Depth	Quantity	Unit/ Remarks	Rate
	270.00	285.00		1	15.00	1.20	1.20	1.20		18.00		
	285.00	300.00		1	15.00	1.20	1.20	1.20		18.00		
	300.00	315.00		1	15.00	1.20	1.20	1.20		18.00		
	315.00	330.00		1	15.00	1.20	1.20	1.20		18.00		
	330.00	338.50		1	8.50	1.20	1.20	1.20		10.20		
									Total Quantity	**5407.69**	Sqm	28.55
5	KSRRB M500-17. Providing and laying dense graded bituminous macadam using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and, transporting the hot mix to work site, laying to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH table 500-10 complete in all respects complete as per specifications. Clause 505 of morth V revision using 40/60 TPH capacity H.M.P. with mechanical paver Gr-II (50mm to 75mm) with 4.5% VG-30 Bitumen. Page No. 160/ Item No. 21.17.6/ PWD SR 2018-19 Issue Rates											
	Virupakshanagar 5th cross road.											
	0.00	15.00		1.00	15.00	6.80	5.90	6.35	0.05	4.76		
	15.00	30.00		1.00	15.00	5.90	5.90	5.90	0.05	4.43		
	30.00	45.00		1.00	15.00	5.90	5.80	6.00	0.05	4.50		
	45.00	60.00		1.00	15.00	6.30	5.80	6.05	0.05	4.54		
	60.00	75.00		1.00	15.00	5.80	5.40	5.60	0.05	4.20		
	75.00	90.00		1.00	15.00	5.40	5.40	6.00	0.05	4.50		
	90.00	105.00		1.00	15.00	5.40	5.70	5.55	0.05	4.16		
	105.00	120.00		1.00	15.00	5.70	5.70	5.70	0.05	4.28		
	120.00	135.00		1.00	15.00	5.70	5.60	5.65	0.05	4.24		
	135.00	150.00		1.00	15.00	5.60	5.60	5.60	0.05	4.20		
	150.00	165.00		1.00	15.00	5.60	4.90	5.25	0.05	3.94		
	165.00	180.00		1.00	15.00	4.90	4.90	4.90	0.05	3.68		
	180.00	195.00		1.00	15.00	4.90	5.20	5.05	0.05	3.79		
	195.00	210.00		1.00	15.00	5.20	5.20	5.20	0.05	3.90		
	210.00	214.00		1.00	4.00	5.20	5.30	5.25	0.05	1.05		
	Virupakshanagar 4th cross road.											
	0.00	15.00		1.00	15.00	6.10	6.30	6.20	0.05	4.65		
	15.00	30.00		1.00	15.00	6.30	6.30	6.30	0.05	4.73		
	30.00	45.00		1.00	15.00	6.30	5.90	6.00	0.05	4.50		
	45.00	60.00		1.00	15.00	6.30	5.90	6.10	0.05	4.58		
	60.00	75.00		1.00	15.00	5.90	5.30	5.60	0.05	4.20		
	75.00	90.00		1.00	15.00	5.30	5.30	6.00	0.05	4.50		
	90.00	105.00		1.00	15.00	5.30	4.60	4.95	0.05	3.71		
	105.00	120.00		1.00	15.00	4.60	4.60	4.60	0.05	3.45		
	120.00	135.00		1.00	15.00	4.60	4.30	4.45	0.05	3.34		
	135.00	150.00		1.00	15.00	4.30	4.30	4.30	0.05	3.23		
	150.00	165.00		1.00	15.00	4.30	4.40	4.35	0.05	3.26		
	165.00	180.00		1.00	15.00	4.40	4.40	4.40	0.05	3.30		
	180.00	195.00		1.00	15.00	4.40	4.60	4.50	0.05	3.38		
	195.00	208.00		1.00	13.00	4.60	4.60	4.60	0.05	2.99		
	Virupakshanagar 3rd cross road.											
	0.00	15.00		1.00	15.00	8.10	6.40	7.25	0.05	5.44		
	15.00	30.00		1.00	15.00	6.40	6.40	6.40	0.05	4.80		
	30.00	45.00		1.00	15.00	6.40	5.60	6.00	0.05	4.50		
	45.00	60.00		1.00	15.00	6.30	5.60	5.95	0.05	4.46		
	60.00	75.00		1.00	15.00	5.60	5.20	5.40	0.05	4.05		
	75.00	90.00		1.00	15.00	5.20	5.20	6.00	0.05	4.50		
	90.00	105.00		1.00	15.00	5.20	5.90	5.55	0.05	4.16		
	105.00	120.00		1.00	15.00	5.90	5.90	5.90	0.05	4.43		
	120.00	135.00		1.00	15.00	5.90	5.50	5.70	0.05	4.28		
	135.00	150.00		1.00	15.00	5.50	5.50	5.50	0.05	4.13		
	150.00	165.00		1.00	15.00	5.50	5.20	5.35	0.05	4.01		
	165.00	180.00		1.00	15.00	5.20	5.20	5.20	0.05	3.90		

Item No	Description / Chainage		Side	Nos	Length	Width B1	Width B2	Width Avg B	Depth	Quantity	Unit/ Remarks	Rate	Amount
	180.00	195.00		1.00	15.00	5.20	8.20	6.70	0.05	5.03			
	195.00	210.00		1.00	15.00	8.20	8.20	8.20	0.05	6.15			
	210.00	225.00		1.00	15.00	8.20	6.20	7.20	0.05	5.40			
	225.00	240.00		1.00	15.00	6.20	6.20	6.20	0.05	4.65			
	240.00	255.00		1.00	15.00	6.20	6.30	6.25	0.05	4.69			
	255.00	270.00		1.00	15.00	6.30	6.30	6.30	0.05	4.73			
	270.00	285.00		1.00	15.00	6.30	7.50	6.90	0.05	5.18			
	285.00	300.00		1.00	15.00	7.50	7.50	7.50	0.05	5.63			
	300.00	308.00		1.00	8.00	7.50	7.50	7.50	0.05	3.00			
	308.00	310.00		0.00	0.00	0.00	0.00	0.00	0.05	0.00			
	310.00	325.00		1.00	15.00	0.00	7.30	3.65	0.05	2.74			
	325.00	330.00		1.00	5.00	7.30	7.30	7.30	0.05	1.83			
	Profile correction												
	8th Main Deshabandu nagar												
	30.00	57.00		1.00	27.00	2.00	1.50	1.75	0.05	2.36			
	7th Main Deshabandu nagar												
	60.00	82.00		1.00	22.00	2.20	1.50	1.85	0.05	2.04			
	100.00	118.00		1.00	18.00	2.00	1.70	1.85	0.05	1.67			
	4th main Deshabandu nagar												
	0.00	36.00		1.00	36.00	1.80	2.00	1.90	0.05	3.42			
	0.00												
	3rd main Deshabandu nagar												
	55.00	85.00		1.00	30.00	1.50	1.50	1.50	0.05	2.25			
	2nd Main Road Deshabandu nagar												
	25.00	45.00		1.00	20.00	1.80	1.50	1.65	0.05	1.65			
	55.00	75.00		1.00	20.00	1.20	1.50	1.35	0.05	1.35			
	Renukamba Temple Road												
	0.00	20.00		1.00	20.00	1.80	1.50	1.65	0.05	1.65			
	55.00	86.00		1.00	31.00	1.20	1.50	1.35	0.05	2.09			
	135.00	160.00		1.00	25.00	1.20	1.50	1.35	0.05	1.69			
	3rd Cross Road G Byrappa Garden												
	15.00	26.00		1.00	11.00	1.80	1.50	1.65	0.05	0.91			
	50.00	65.00		1.00	15.00	1.20	1.50	1.35	0.05	1.01			
	2nd Main Road												
	0.00	31.00		1.00	31.00	1.20	1.50	1.35	0.05	2.09			
	65.00	100.00		1.00	35.00	1.20	1.50	1.35	0.05	2.36			
	2nd B cross Ramiah Garden												
	50.00	95.00		1.00	45.00	1.10	1.50	1.30	0.05	2.93			
	5th Main Deshabandu nagar												
	40.00	75.00		1.00	35.00	1.50	2.00	1.75	0.05	3.06			
	100.00	110.00		1.00	10.00	1.50	2.00	1.75	0.05	0.88			
	2nd Cross Byrappa Garden												
	0.00	18.00		1.00	18.00	1.50	2.00	1.75	0.05	1.58			
	110.00	145.00		1.00	35.00	1.10	1.80	1.45	0.05	2.54			
	Family Enclave Road												
	55.00	80.00		1.00	25.00	1.10	1.80	1.45	0.05	1.81			
	95.00	112.00		1.00	17.00	1.50	2.00	1.75	0.05	1.49			
	Krishna Temple Road												
	0.00	15.00		1.00	15.00	4.60	5.20	4.90	0.05	3.68			
	15.00	30.00		1.00	15.00	5.20	3.70	4.45	0.05	3.34			
	30.00	45.00		1.00	15.00	3.70	3.60	3.65	0.05	2.74			
	45.00	60.00		1.00	15.00	3.60	3.80	3.70	0.05	2.78			
	60.00	75.00		1.00	15.00	3.80	3.70	3.75	0.05	2.81			
	75.00	90.00		1.00	15.00	3.70	3.40	3.55	0.05	2.66			
	90.00	105.00		1.00	15.00	3.40	3.60	3.50	0.05	2.63			

BOQ Item No	Description Chainage		Side	Nos	Length	Width B1	Width B2	Width Avg B	Depth	Quantity	Unit/ Remarks	Rate
	105.00	120.00		1.00	15.00	3.60	4.00	3.80	0.05	2.85		
	120.00	135.00		1.00	15.00	4.00	4.00	4.00	0.05	3.00		
	135.00	140.00		1.00	5.00	4.00	4.90	4.45	0.05	1.11		
	Shri Chamundeshwari Temple Road											
	0.00	4.50		1.00	4.50	7.10	5.50	6.30	0.05	1.42		
	4.50	15.00		1.00	10.50	5.50	6.20	5.85	0.05	3.07		
	15.00	19.70		1.00	4.70	6.20	7.40	6.80	0.05	1.60		
	19.70	30.00		1.00	10.30	7.40	7.00	7.20	0.05	3.71		
	30.00	45.00		1.00	15.00	7.00	6.30	6.65	0.05	4.99		
	45.00	60.00		1.00	15.00	6.30	7.00	6.65	0.05	4.99		
	60.00	75.00		1.00	15.00	7.00	7.20	7.10	0.05	5.33		
	75.00	90.00		1.00	15.00	7.20	6.90	7.05	0.05	5.29		
	90.00	105.00		1.00	15.00	6.90	6.30	6.60	0.05	4.95		
	105.00	120.00		1.00	15.00	6.30	6.30	6.30	0.05	4.73		
	120.00	135.00		1.00	15.00	6.30	4.70	5.50	0.05	4.13		
	135.00	150.00		1.00	15.00	4.70	7.40	6.05	0.05	4.54		
	150.00	165.00		1.00	15.00	7.40	6.20	6.80	0.05	5.10		
	165.00	175.70		1.00	10.70	6.20	4.10	5.15	0.05	2.76		
	Anjaneyaswamy layout Ganga street											
	0.00	15.00		1.00	15.00	6.30	6.10	6.20	0.05	4.65		
	15.00	30.00		1.00	15.00	6.10	5.50	5.80	0.05	4.35		
	30.00	45.00		1.00	15.00	5.50	5.40	5.45	0.05	4.09		
	45.00	60.00		1.00	15.00	5.40	5.00	5.20	0.05	3.90		
	60.00	75.00		1.00	15.00	5.00	5.50	5.25	0.05	3.94		
	75.00	90.00		1.00	15.00	5.50	5.80	5.65	0.05	4.24		
	90.00	105.00		1.00	15.00	5.80	5.70	5.75	0.05	4.31		
	105.00	120.00		1.00	15.00	5.70	5.80	5.75	0.05	4.31		
	120.00	135.00		1.00	15.00	5.80	4.60	5.20	0.05	3.90		
	135.00	150.00		1.00	15.00	4.60	4.10	4.35	0.05	3.26		
	150.00	165.00		1.00	15.00	4.10	4.50	4.30	0.05	3.23		
	165.00	180.00		1.00	15.00	4.50	5.00	4.75	0.05	3.56		
	180.00	195.00		1.00	15.00	5.00	5.30	5.15	0.05	3.86		
	195.00	210.00		1.00	15.00	5.30	5.70	5.50	0.05	4.13		
	210.00	225.00		1.00	15.00	5.70	4.00	4.85	0.05	3.64		
	225.00	240.00		1.00	15.00	4.00	4.90	4.45	0.05	3.34		
	240.00	255.00		1.00	15.00	4.90	5.00	4.95	0.05	3.71		
	255.00	261.00		1.00	6.00	5.00	5.00	5.00	0.05	1.50		
	Anjaneyaswamy layout Krishna street											
	0.00	15.00		1.00	15.00	5.50	4.60	5.05	0.05	3.79		
	15.00	30.00		1.00	15.00	4.60	5.20	4.90	0.05	3.68		
	30.00	45.00		1.00	15.00	5.20	5.20	5.20	0.05	3.90		
	45.00	60.00		1.00	15.00	5.20	5.60	5.40	0.05	4.05		
	60.00	75.00		1.00	15.00	5.60	5.70	5.65	0.05	4.24		
	75.00	90.00		1.00	15.00	5.70	4.90	5.30	0.05	3.98		
	90.00	105.00		1.00	15.00	4.90	4.40	4.65	0.05	3.49		
	105.00	120.00		1.00	15.00	4.40	4.90	4.65	0.05	3.49		
	120.00	130.00		1.00	10.00	4.90	5.50	5.20	0.05	2.60		
	Telicom Layout 4th Cross Road											
	0.00	13.50		1.00	13.50	7.20	7.20	7.20	0.05	4.86		
	13.50	15.00		1.00	1.50	7.20	7.30	7.25	0.05	0.54		
	15.00	16.00		1.00	1.00	7.30	7.30	7.30	0.05	0.37		
	16.00	30.00		1.00	14.00	7.30	7.30	7.30	0.05	5.11		
	30.00	45.00		1.00	15.00	7.30	7.50	7.40	0.05	5.55		
	45.00	59.00		1.00	14.00	7.50	7.50	7.50	0.05	5.25		
	59.00	60.00		1.00	1.00	7.50	4.70	6.10	0.05	0.31		
	60.00	63.00		1.00	3.00	4.70	4.70	4.70	0.05	0.71		
	63.00	75.00		1.00	12.00	4.70	7.40	6.05	0.05	3.63		
	75.00	78.00		1.00	3.00	7.40	7.40	7.40	0.05	1.11		
	78.00	85.00		1.00	7.00	7.40	7.40	7.40	0.05	2.59		
	85.00	90.00		1.00	5.00	7.40	4.50	5.95	0.05	1.49		
	90.00	98.00		1.00	8.00	4.50	4.50	4.50	0.05	1.80		
	98.00	105.00		1.00	7.00	4.50	6.80	5.65	0.05	1.98		

Item No	Description Chainage		Side	Nos	Length	Width B1	Width B2	Width Avg B	Depth	Quantity	Unit/ Remarks	Rate	Amount
	105.00	110.00		1.00	5.00	6.80	6.80	6.80	0.05	1.70			
	110.00	115.00		1.00	5.00	6.80	6.00	6.40	0.05	1.60			
	115.00	125.00		1.00	10.00	6.00	6.00	6.00	0.05	3.00			
	125.00	133.00		1.00	8.00	6.00	6.00	6.00	0.05	2.40			
	133.00	140.00		1.00	7.00	6.00	5.00	5.50	0.05	1.93			
	140.00	151.50		1.00	11.50	5.00	5.00	5.00	0.05	2.88			
	151.50	160.00		1.00	8.50	5.00	6.20	5.60	0.05	2.38			
	160.00	171.50		1.00	11.50	6.20	6.70	6.45	0.05	3.71			
	2nd Main Road Telicom Layout												
	0.00	15.00		1.00	15.00	6.80	8.10	7.45	0.05	5.59			
	15.00	30.00		1.00	15.00	8.10	7.90	8.00	0.05	6.00			
	30.00	45.00		1.00	15.00	7.90	7.00	7.45	0.05	5.59			
	45.00	60.00		1.00	15.00	7.00	6.70	6.85	0.05	5.14			
	60.00	75.00		1.00	15.00	6.70	7.00	6.85	0.05	5.14			
	75.00	78.00		1.00	3.00	7.00	7.00	7.00	0.05	1.05			
	78.00	90.00		1.00	12.00	7.00	9.60	8.30	0.05	4.98			
	90.00	91.00		1.00	1.00	9.60	9.60	9.60	0.05	0.48			
	91.00	105.00		1.00	14.00	9.60	8.30	8.95	0.05	6.27			
	105.00	109.00		1.00	4.00	8.30	8.30	8.30	0.05	1.66			
	109.00	120.00		1.00	11.00	8.30	9.50	8.90	0.05	4.90			
	120.00	126.00		1.00	6.00	9.50	9.50	9.50	0.05	2.85			
	126.00	135.00		1.00	9.00	9.50	7.50	8.50	0.05	3.83			
	135.00	143.50		1.00	8.50	7.50	7.50	7.50	0.05	3.19			
	143.50	150.00		1.00	6.50	7.50	9.90	8.70	0.05	2.83			
	150.00	165.00		1.00	15.00	9.90	9.20	9.55	0.05	7.16			
	165.00	180.00		1.00	15.00	9.20	9.20	9.20	0.05	6.90			
	180.00	185.00		1.00	5.00	9.20	9.20	9.20	0.05	2.30			
	185.00	195.00		1.00	10.00	9.20	9.20	9.20	0.05	4.60			
	195.00	208.00		1.00	13.00	9.20	9.20	9.20	0.05	5.98			
	208.00	210.00		1.00	2.00	9.20	8.80	9.00	0.05	0.90			
	210.00	220.00		1.00	10.00	8.80	8.80	8.80	0.05	4.40			
	220.00	225.00		1.00	5.00	8.80	8.70	8.75	0.05	2.19			
	225.00	240.00		1.00	15.00	8.70	9.30	9.00	0.05	6.75			
	240.00	245.00		1.00	5.00	9.30	9.30	9.30	0.05	2.33			
	245.00	250.00		1.00	5.00	9.30	9.30	9.30	0.05	2.33			
	250.00	253.00		1.00	3.00	9.30	7.10	8.20	0.05	1.23			
	253.00	255.00		1.00	2.00	7.10	7.10	7.10	0.05	0.71			
	255.00	270.00		1.00	15.00	7.10	5.90	6.50	0.05	4.88			
	270.00	285.00		1.00	15.00	5.90	7.20	6.55	0.05	4.91			
	285.00	300.00		1.00	15.00	7.20	7.00	7.10	0.05	5.33			
	300.00	315.00		1.00	15.00	7.00	6.30	6.65	0.05	4.99			
	315.00	330.00		1.00	15.00	6.30	6.40	6.35	0.05	4.76			
	330.00	345.00		1.00	15.00	6.40	6.50	6.45	0.05	4.84			
	345.00	360.00		1.00	15.00	6.50	6.30	6.40	0.05	4.80			
	360.00	375.00		1.00	15.00	6.30	5.90	6.10	0.05	4.58			
	375.00	390.00		1.00	15.00	5.90	6.00	5.95	0.05	4.46			
	390.00	405.00		1.00	15.00	6.00	6.00	6.00	0.05	4.50			
	405.00	417.00		1.00	12.00	6.00	7.00	6.50	0.05	3.90			
	Ganesh Nagar Road												
	0.00	15.00		1.00	15.00	5.70	5.40	5.55	0.05	4.16			
	15.00	30.00		1.00	15.00	5.40	6.00	5.70	0.05	4.28			
	30.00	45.00		1.00	15.00	6.00	6.40	6.20	0.05	4.65			
	45.00	60.00		1.00	15.00	6.40	6.50	6.45	0.05	4.84			
	60.00	75.00		1.00	15.00	6.50	8.10	7.30	0.05	5.48			
	75.00	90.00		1.00	15.00	8.10	6.60	7.35	0.05	5.51			
	90.00	105.00		1.00	15.00	6.60	4.60	5.60	0.05	4.20			
	105.00	120.00		1.00	15.00	4.60	4.50	4.55	0.05	3.41			
	120.00	135.00		1.00	15.00	4.50	4.30	4.40	0.05	3.30			
	135.00	150.00		1.00	15.00	4.30	6.20	5.25	0.05	3.94			
	150.00	165.00		1.00	15.00	6.20	4.70	5.45	0.05	4.09			
	165.00	180.00		1.00	15.00	4.70	5.30	5.00	0.05	3.75			
	180.00	195.00		1.00	15.00	5.30	5.30	5.30	0.05	3.98			
	195.00	210.00		1.00	15.00	5.30	4.10	4.70	0.05	3.53			
	210.00	225.00		1.00	15.00	4.10	6.70	5.40	0.05	4.05			
	225.00	240.00		1.00	15.00	6.70	6.00	6.35	0.05	4.76			

BOQ Item No	Description Chainage		Side	Nos	Length	Width B1	Width B2	Width Avg B	Depth	Quantity	Unit/ Remarks	Rate
	240.00	255.00		1.00	15.00	6.00	6.10	6.05	0.05	4.54		
	255.00	270.00		1.00	15.00	6.10	6.30	6.20	0.05	4.65		
	270.00	285.00		1.00	15.00	6.30	8.40	7.35	0.05	5.51		
	285.00	300.00		1.00	15.00	8.40	10.20	9.30	0.05	6.98		
	300.00	315.00		1.00	15.00	10.20	15.20	12.70	0.05	9.53		
	315.00	330.00		1.00	15.00	15.20	18.90	17.05	0.05	12.79		
	330.00	338.50		1.00	8.50	18.90	20.30	19.60	0.05	8.33		
	2nd Cross Road Gas Godown Road											
	0.00	15.00		1.00	15.00	4.60	4.80	4.70	0.05	3.53		
	15.00	30.00		1.00	15.00	4.80	5.20	5.00	0.05	3.75		
	30.00	45.00		1.00	15.00	5.20	4.80	5.00	0.05	3.75		
	45.00	60.00		1.00	15.00	4.80	5.50	5.15	0.05	3.86		
	60.00	65.00		1.00	5.00	5.50	5.20	5.35	0.05	1.34		
	65.00	68.00		1.00	3.00	5.20	13.10	9.15	0.05	1.37		
	68.00	71.50		1.00	3.50	13.10	11.80	12.45	0.05	2.18		
										795.75		
									BOQ	**735.10**		
									Qty Upto 125%	**795.75**	**Cum**	6,643.88
6	KSRRB 500-2. Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH specification clause 501 Page No. 158/ Item No. 21.2/ PWD SR 2018-19											
	8th Main Deshabandu nagar											
	0.00	30.00		1	30.00	6.00	3.70	4.85		145.50		
	30.00	60.00		1	30.00	3.70	4.00	3.85		115.50		
	60.00	90.00		1	30.00	4.00	4.00	4.00		120.00		
	90.00	116.00		1	26.00	4.00	3.50	3.75		97.50		
	7th Main Deshabandu nagar											
	0.00	30.00		1	30.00	6.00	3.60	4.80		144.00		
	30.00	60.00		1	30.00	3.60	3.50	3.55		106.50		
	60.00	90.00		1	30.00	3.50	4.30	3.90		117.00		
	90.00	120.00		1	30.00	4.30	4.10	4.20		126.00		
	120.00	150.00		1	30.00	4.10	3.40	3.75		112.50		
	150.00	180.00		1	30.00	3.40	3.80	3.60		108.00		
	180.00	189.00		1	9.00	2.20	2.20	2.20		19.80		
	189.00	198.00		1	9.00	2.40	2.40	2.40		21.60		
	4th main Deshabandu nagar											
	0.00	30.00		1	30.00	4.50	4.00	4.25		127.50		
	30.00	60.00		1	30.00	4.00	3.50	3.75		112.50		
	60.00	90.00		1	30.00	3.50	4.00	3.75		112.50		
	90.00	120.00		1	30.00	4.00	4.20	4.10		123.00		
	120.00	150.00		1	30.00	4.20	4.30	4.25		127.50		
	150.00	157.00		1	7.00	4.30	4.20	4.25		29.75		
	3rd main Deshabandu nagar											
	0.00	30.00		1	30.00	6.00	3.90	4.95		148.50		
	30.00	60.00		1	30.00	3.90	3.90	3.90		117.00		
	60.00	87.00		1	27.00	3.90	4.50	4.20		113.40		
	87.00	90.00		1	3.00	4.40	4.40	4.40		13.20		
	90.00	110.00		1	20.00	4.40	3.50	3.95		79.00		
	2nd Main Road Deshabandu nagar											
	0.00	26.00		1	26.00	4.40	5.50	4.95		128.70		
	26.00	50.00		1	24.00	5.00	5.60	5.30		127.20		
	50.00	60.00		1	10.00	5.60	5.30	5.45		54.50		
	60.00	90.00		1	30.00	5.30	5.80	5.55		166.50		
	101.00	118.00		1	17.00	5.40	4.80	5.10		86.70		

Description		Side	Nos	Length	Width			Depth	Quantity	Unit/ Remarks	Rate	Amount
Chainage					B1	B2	Avg B					
Renukamba Temple Road												
0.00	30.00		1	30.00	5.50	5.60	5.55					
30.00	60.00		1	30.00	5.60	4.40	5.00		166.50			
60.00	90.00		1	30.00	4.40	4.00	4.20		150.00			
90.00	93.00		1	3.00	4.00	3.80	3.90		126.00			
93.00	120.00		1	27.00	6.40	6.40	6.40		11.70			
120.00	136.00		1	16.00	6.40	4.70	5.55		172.80			
136.00	150.00		1	14.00	4.70	3.80	4.25		88.80			
150.00	180.00		1	30.00	3.80	4.50	4.15		59.50			
180.00	210.00		1	30.00	4.50	4.60	4.55		124.50			
210.00	228.00		1	18.00	4.60	4.00	4.30		136.50			
									77.40			
rd Cross Road G Byrappa Garden												
0.00	30.00		1	30.00	4.20	3.70	3.95		118.50			
30.00	60.00		1	30.00	3.70	3.60	3.65		109.50			
60.00	90.00		1	30.00	3.60	5.20	4.40		132.00			
90.00	94.00		1	4.00	5.20	5.20	5.20		20.80			
nd A cross G Byrappa Garden												
0.00	11.00		1	11.00	5.90	5.30	5.60		61.60			
11.00	14.00		1	3.00	5.30	5.30	5.30		15.90			
14.00	30.00		1	16.00	3.40	4.70	4.05		64.80			
30.00	47.50		1	17.50	4.70	5.10	4.90		85.75			
47.50	52.00		1	4.50	2.80	3.00	2.90		13.05			
nd Main Road												
0.00	18.00		1	18.00	7.00	4.80	5.90		106.20			
18.00	26.00		1	8.00	4.80	5.00	4.90		39.20			
26.00	40.00		1	14.00	5.00	4.50	4.75		66.50			
40.00	60.00		1	20.00	4.50	4.30	4.40		88.00			
60.00	90.00		1	30.00	4.30	5.20	4.75		142.50			
90.00	120.00		1	30.00	5.20	4.70	4.95		148.50			
120.00	150.00		1	30.00	4.70	4.00	4.35		130.50			
150.00	180.00		1	30.00	4.00	4.70	4.35		130.50			
180.00	190.00		1	10.00	4.70	4.30	4.50		45.00			
2nd B cross Ramiah Garden												
0.00	30.00		1	30.00	7.20	5.60	6.40		192.00			
30.00	60.00		1	30.00	5.60	3.80	4.70		141.00			
60.00	90.00		1	30.00	3.80	4.00	3.90		117.00			
90.00	94.50		1	4.50	4.00	4.00	4.00		18.00			
94.50	98.00		1	3.50	2.50	2.50	2.50		8.75			
98.00	117.50		1	19.50	4.20	4.40	4.30		83.85			
5th cross Ramiah Garden												
0.00	30.00		1	30.00	4.80	4.80	4.80		144.00			
30.00	39.50		1	9.50	4.80	5.20	5.00		47.50			
2nd Cross Ramaiah Garden												
0.00	30.00		1	30.00	4.50	4.20	4.35		130.50			
30.00	37.00		1	7.00	4.20	3.50	3.85		26.95			
5th Main Deshabandu nagar												
0.00	30.00		1	30.00	8.60	5.00	6.80		204.00			
30.00	60.00		1	30.00	5.00	4.80	4.90		147.00			
60.00	90.00		1	30.00	4.80	4.70	4.75		142.50			
90.00	120.00		1	30.00	4.70	4.50	4.60		138.00			
120.00	150.00		1	30.00	4.50	4.30	4.40		132.00			
150.00	166.00		1	16.00	4.30	5.60	4.95		79.20			
4th 1st b Cross Deshabandunagar												
0.00	24.40		1	24.40	4.30	4.30	4.30		104.92			
24.40	47.00		1	22.60	3.60	4.40	4.00		90.40			

BOQ Item No	Description		Side	Nos	Length	Width			Depth	Quantity	Unit/ Remarks	Rate
	Chainage					B1	B2	Avg B				
	2nd Cross Byrappa Garden											
	0.00	30.00		1	30.00	3.70	3.90	3.80		114.00		
	30.00	60.00		1	30.00	3.90	4.90	4.40		132.00		
	60.00	90.00		1	30.00	4.90	5.00	4.95		148.50		
	90.00	120.00		1	30.00	5.00	4.50	4.75		142.50		
	120.00	150.00		1	30.00	4.50	4.50	4.50		135.00		
	150.00	180.00		1	30.00	4.50	4.50	4.50		135.00		
	180.00	187.00		1	7.00	4.50	4.50	4.50		31.50		
	2nd B Cross Ramiah Layout											
	0.00	30.00		1	30.00	5.60	4.20	4.90		147.00		
	30.00	60.00		1	30.00	4.20	5.00	4.60		138.00		
	60.00	63.50		1	3.50	5.00	5.00	5.00		17.50		
	Family Enclave Road											
	0.00	30.00		1	30.00	5.90	6.20	6.05		181.50		
	30.00	60.00		1	30.00	6.20	5.60	5.90		177.00		
	60.00	90.00		1	30.00	5.60	5.40	5.50		165.00		
	90.00	112.00		1	22.00	5.40	5.30	5.35		117.70		
	2nd B cross G Byrappa Garden											
	0.00	30.00		1	30.00	4.50	4.40	4.45		133.50		
	30.00	60.00		1	30.00	4.40	4.40	4.40		132.00		
	60.00	77.00		1	17.00	4.40	4.30	4.35		73.95		
	11 th Main Yarappa Garden											
	0.00	15.00		1	15.00	6.40	5.20	5.80		87.00		
	15.00	30.00		1	15.00	5.20	5.70	5.45		81.75		
	30.00	45.00		1	15.00	5.70	5.50	5.60		84.00		
	45.00	60.00		1	15.00	5.50	5.20	5.35		80.25		
	60.00	75.00		1	15.00	5.20	5.40	5.30		79.50		
	75.00	90.00		1	15.00	5.40	5.60	5.50		82.50		
	90.00	105.00		1	15.00	5.60	5.00	5.30		79.50		
	105.00	120.00		1	15.00	5.00	5.40	5.20		78.00		
	120.00	135.00		1	15.00	5.40	5.90	5.65		84.75		
	135.00	150.00		1	15.00	5.90	5.60	5.75		86.25		
	150.00	165.00		1	15.00	5.60	5.80	5.70		85.50		
	165.00	180.00		1	15.00	5.80	6.20	6.00		90.00		
	180.00	195.00		1	15.00	6.20	6.10	6.15		92.25		
	195.00	210.00		1	15.00	6.10	6.20	6.15		92.25		
	210.00	224.40		1	14.40	6.20	6.00	6.10		87.84		
	3rd cross Yarappa Garden											
	0.00	15.00		1	15.00	4.80	3.90	4.35		65.25		
	15.00	30.00		1	15.00	3.90	3.70	3.80		57.00		
	30.00	45.00		1	15.00	3.70	3.80	3.75		56.25		
	45.00	60.00		1	15.00	3.80	2.90	3.35		50.25		
	60.00	75.00		1	15.00	2.90	4.40	3.65		54.75		
	75.00	82.20		1	7.20	4.40	4.20	4.30		30.96		
	3rd C cross Road Yarappa Garden											
	0.00	15.00		1	15.00	5.00	4.90	4.95		74.25		
	15.00	30.00		1	15.00	4.90	4.80	4.85		72.75		
	30.00	45.00		1	15.00	4.80	4.90	4.85		72.75		
	45.00	57.00		1	12.00	4.90	4.50	4.70		56.40		
	3rd A cross Road Yarappa Garden											
	0.00	15.00		1	15.00	4.10	4.00	4.05		60.75		
	15.00	28.70		1	13.70	4.00	3.80	3.90		53.43		
	3rd A cross Road Yarappa Garden											
	0.00	15.00		1	15.00	3.50	3.50	3.50		52.50		
	15.00	32.30		1	17.30	3.50	4.60	4.05		70.07		

Item No	Description Chainage		Side	Nos	Length	Width B1	Width B2	Width Avg B	Depth	Quantity	Unit/ Remarks	Rate	Amount
3rd A cross Road Yarappa Garden													
	0.00	15.00		1	15.00	3.40	2.40	2.90		43.50			
	15.00	21.80		1	6.80	2.40	2.40	2.40		16.32			
3rd A cross Road opp Road Yarappa Garden													
	0.00	15.00		1	15.00	5.10	3.70	4.40		66.00			
	15.00	30.00		1	15.00	3.70	3.80	3.75		56.25			
	30.00	45.00		1	15.00	3.80	4.20	4.00		60.00			
	45.00	49.10		1	4.10	4.20	4.70	4.45		18.25			
2nd cross Road Yarappa Garden													
	0.00	15.00		1	15.00	5.70	5.10	5.40		81.00			
	15.00	30.00		1	15.00	5.10	4.70	4.90		73.50			
	30.00	45.00		1	15.00	4.70	3.70	4.20		63.00			
	45.00	60.00		1	15.00	3.70	3.80	3.75		56.25			
	60.00	75.60		1	15.60	3.80	4.40	4.10		63.96			
1st Main Road Chikkvenkatappa layout													
	0.00	15.00		1	15.00	5.20	4.40	4.80		72.00			
	15.00	30.00		1	15.00	4.40	4.40	4.40		66.00			
	30.00	45.00		1	15.00	4.40	4.40	4.40		66.00			
	45.00	60.00		1	15.00	4.40	4.90	4.65		69.75			
	60.00	70.00		1	10.00	4.90	7.50	6.20		62.00			
	70.00	75.00		1	5.00	7.50	7.20	7.35		36.75			
	75.00	90.00		1	15.00	7.20	6.00	6.60		99.00			
	90.00	105.00		1	15.00	6.00	5.70	5.85		87.75			
	105.00	120.00		1	15.00	5.70	5.20	5.45		81.75			
	120.00	135.00		1	15.00	5.20	5.00	5.10		76.50			
	135.00	151.30		1	16.30	5.00	5.00	5.00		81.50			
Renukamba Temple Road													
	0.00	15.00		1	15.00	6.50	5.20	5.85		87.75			
	15.00	30.00		1	15.00	5.20	5.70	5.45		81.75			
	30.00	45.00		1	15.00	5.70	5.70	5.70		85.50			
	45.00	60.00		1	15.00	5.70	5.40	5.55		83.25			
	60.00	75.00		1	15.00	5.40	5.60	5.50		82.50			
	75.00	90.00		1	15.00	5.60	5.40	5.50		82.50			
	90.00	105.00		1	15.00	5.40	5.40	5.40		81.00			
	105.00	113.00		1	8.00	5.40	5.50	5.45		43.60			
Renukamba Temple Road Cross Road A													
	0.00	15.00		1	15.00	6.50	5.80	6.15		92.25			
	15.00	30.00		1	15.00	5.80	5.10	5.45		81.75			
	30.00	45.00		1	15.00	5.10	5.20	5.15		77.25			
	45.00	60.00		1	15.00	5.20	5.20	5.20		78.00			
	60.00	75.00		1	15.00	5.20	4.50	4.85		72.75			
	75.00	90.00		1	15.00	4.50	4.60	4.55		68.25			
Renukamba Temple Road Cross Road B													
	0.00	15.00		1	15.00	6.40	3.90	5.15		77.25			
	15.00	30.00		1	15.00	3.90	3.90	3.90		58.50			
	30.00	45.00		1	15.00	3.90	4.00	3.95		59.25			
	45.00	60.00		1	15.00	4.00	3.90	3.95		59.25			
	60.00	75.00		1	15.00	3.90	3.60	3.75		56.25			
	75.00	90.00		1	15.00	3.60	4.10	3.85		57.75			
	90.00	105.00		1	15.00	4.10	4.20	4.15		62.25			
	105.00	120.00		1	15.00	4.20	4.80	4.50		67.50			
	120.00	135.00		1	15.00	4.80	5.70	5.25		78.75			
	135.00	150.00		1	15.00	5.70	5.50	5.60		84.00			
	150.00	165.00		1	15.00	5.50	4.50	5.00		75.00			
	165.00	180.00		1	15.00	4.50	5.70	5.10		76.50			
	180.00	195.00		1	15.00	5.70	5.10	5.40		81.00			
	195.00	208.80		1	13.80	5.10	5.40	5.25		72.45			

BOQ Item No	Description Chainage		Side	Nos	Length	Width B1	Width B2	Width Avg B	Depth	Quantity	Unit/ Remarks	Rate
	Krishna Temple Road											
	0.00	15.00		1	15.00	4.60	5.20	4.90		73.50		
	15.00	30.00		1	15.00	5.20	3.70	4.45		66.75		
	30.00	45.00		1	15.00	3.70	3.60	3.65		54.75		
	45.00	60.00		1	15.00	3.60	3.80	3.70		55.50		
	60.00	75.00		1	15.00	3.80	3.70	3.75		56.25		
	75.00	90.00		1	15.00	3.70	3.40	3.55		53.25		
	90.00	105.00		1	15.00	3.40	3.60	3.50		52.50		
	105.00	120.00		1	15.00	3.60	4.00	3.80		57.00		
	120.00	135.00		1	15.00	4.00	4.00	4.00		60.00		
	135.00	140.00		1	5.00	4.00	4.90	4.45		22.25		
	2nd Cross Road Gas Godown Road											
	0.00	15.00		1	15.00	4.60	4.80	4.70		70.50		
	15.00	30.00		1	15.00	4.80	5.20	5.00		75.00		
	30.00	45.00		1	15.00	5.20	4.80	5.00		75.00		
	45.00	60.00		1	15.00	4.80	5.50	5.15		77.25		
	60.00	65.00		1	5.00	5.50	5.20	5.35		26.75		
	65.00	68.00		1	3.00	5.20	13.10	9.15		27.45		
	68.00	71.50		1	3.50	13.10	11.80	12.45		43.58		
	Continuation											
	0.00	15.00		1	15.00	3.80	4.40	4.10		61.50		
	15.00	30.00		1	15.00	4.40	4.70	4.55		68.25		
	30.00	45.00		1	15.00	4.70	5.10	4.90		73.50		
	45.00	60.00		1	15.00	5.10	4.00	4.55		68.25		
	60.00	75.00		1	15.00	4.00	5.20	4.60		69.00		
	75.00	90.00		1	15.00	5.20	3.90	4.55		68.25		
	90.00	100.70		1	10.70	3.90	3.80	3.85		41.20		
	Shri Chamundeshwari Temple Road											
	0.00	4.50		1	4.50	7.10	5.50	6.30		28.35		
	4.50	15.00		1	10.50	5.50	6.20	5.85		61.43		
	15.00	19.70		1	4.70	6.20	7.40	6.80		31.96		
	19.70	30.00		1	10.30	7.40	7.00	7.20		74.16		
	30.00	45.00		1	15.00	7.00	6.30	6.65		99.75		
	45.00	60.00		1	15.00	6.30	7.00	6.65		99.75		
	60.00	75.00		1	15.00	7.00	7.20	7.10		106.50		
	75.00	90.00		1	15.00	7.20	6.90	7.05		105.75		
	90.00	105.00		1	15.00	6.90	6.30	6.60		99.00		
	105.00	120.00		1	15.00	6.30	6.30	6.30		94.50		
	120.00	135.00		1	15.00	6.30	4.70	5.50		82.50		
	135.00	150.00		1	15.00	4.70	7.40	6.05		90.75		
	150.00	165.00		1	15.00	7.40	6.20	6.80		102.00		
	165.00	175.70		1	10.70	6.20	4.10	5.15		55.10		
	Anjaneyaswamy layout Ganga street											
	0.00	15.00		1	15.00	6.30	6.10	6.20		93.00		
	15.00	30.00		1	15.00	6.10	5.50	5.80		87.00		
	30.00	45.00		1	15.00	5.50	5.40	5.45		81.75		
	45.00	60.00		1	15.00	5.40	5.00	5.20		78.00		
	60.00	75.00		1	15.00	5.00	5.50	5.25		78.75		
	75.00	90.00		1	15.00	5.50	5.80	5.65		84.75		
	90.00	105.00		1	15.00	5.80	5.70	5.75		86.25		
	105.00	120.00		1	15.00	5.70	5.80	5.75		86.25		
	120.00	135.00		1	15.00	5.80	4.60	5.20		78.00		
	135.00	150.00		1	15.00	4.60	4.10	4.35		65.25		
	150.00	165.00		1	15.00	4.10	4.50	4.30		64.50		
	165.00	180.00		1	15.00	4.50	5.00	4.75		71.25		
	180.00	195.00		1	15.00	5.00	5.30	5.15		77.25		
	195.00	210.00		1	15.00	5.30	5.70	5.50		82.50		
	210.00	225.00		1	15.00	5.70	4.00	4.85		72.75		
	225.00	240.00		1	15.00	4.00	4.90	4.45		66.75		
	240.00	255.00		1	15.00	4.90	5.00	4.95		74.25		
	255.00	261.00		1	6.00	5.00	5.00	5.00		30.00		

Q Item No	Description Chainage		Side	Nos	Length	Width B1	Width B2	Width Avg B	Depth	Quantity	Unit/ Remarks	Rate	Amount
Anjaneyaswamy layout Krishna street													
	0.00	15.00		1	15.00	5.50	4.60	5.05		75.75			
	15.00	30.00		1	15.00	4.60	5.20	4.90		73.50			
	30.00	45.00		1	15.00	5.20	5.20	5.20		78.00			
	45.00	60.00		1	15.00	5.20	5.60	5.40		81.00			
	60.00	75.00		1	15.00	5.60	5.70	5.65		84.75			
	75.00	90.00		1	15.00	5.70	4.90	5.30		79.50			
	90.00	105.00		1	15.00	4.90	4.40	4.65		69.75			
	105.00	120.00		1	15.00	4.40	4.90	4.65		69.75			
	120.00	130.00		1	10.00	4.90	5.50	5.20		52.00			
3rd Cross Road Anjaneya layout													
	0.00	15.00		1	15.00	3.80	5.40	4.60		69.00			
	15.00	30.00		1	15.00	5.40	5.10	5.25		78.75			
	30.00	45.00		1	15.00	5.10	5.40	5.25		78.75			
	45.00	60.00		1	15.00	5.40	4.70	5.05		75.75			
	60.00	75.00		1	15.00	4.70	4.80	4.75		71.25			
	75.00	90.00		1	15.00	4.80	5.30	5.05		75.75			
	90.00	105.00		1	15.00	5.30	5.60	5.45		81.75			
	105.00	120.00		1	15.00	5.60	5.90	5.75		86.25			
	120.00	141.50		1	21.50	5.90	5.80	5.85		125.78			
Telicom Layout Triveni road 2nd Main Raod													
	0.00	15.00		1	15.00	5.40	5.80	5.60		84.00			
	15.00	30.00		1	15.00	5.80	5.90	5.85		87.75			
	30.00	45.00		1	15.00	5.90	5.90	5.90		88.50			
	45.00	55.00		1	10.00	5.90	5.20	5.55		55.50			
Telicom Layout 4th Cross Road													
	0.00	13.50		1	13.50	7.20	7.20	7.20		97.20			
	13.50	15.00		1	1.50	7.20	7.30	7.25		10.88			
	15.00	16.00		1	1.00	7.30	7.30	7.30		7.30			
	16.00	30.00		1	14.00	7.30	7.30	7.30		102.20			
	30.00	45.00		1	15.00	7.30	7.50	7.40		111.00			
	45.00	59.00		1	14.00	7.50	7.50	7.50		105.00			
	59.00	60.00		1	1.00	7.50	4.70	6.10		6.10			
	60.00	63.00		1	3.00	4.70	4.70	4.70		14.10			
	63.00	75.00		1	12.00	4.70	7.40	6.05		72.60			
	75.00	78.00		1	3.00	7.40	7.40	7.40		22.20			
	78.00	85.00		1	7.00	7.40	7.40	7.40		51.80			
	85.00	90.00		1	5.00	7.40	4.50	5.95		29.75			
	90.00	98.00		1	8.00	4.50	4.50	4.50		36.00			
	98.00	105.00		1	7.00	4.50	6.80	5.65		39.55			
	105.00	110.00		1	5.00	6.80	6.80	6.80		34.00			
	110.00	115.00		1	5.00	6.80	6.00	6.40		32.00			
	115.00	125.00		1	10.00	6.00	6.00	6.00		60.00			
	125.00	133.00		1	8.00	6.00	6.00	6.00		48.00			
	133.00	140.00		1	7.00	6.00	5.00	5.50		38.50			
	140.00	151.50		1	11.50	5.00	5.00	5.00		57.50			
	151.50	160.00		1	8.50	5.00	6.20	5.60		47.60			
	160.00	171.50		1	11.50	6.20	6.70	6.45		74.18			
2nd Main Road Telicom Layout													
	0.00	15.00		1	15.00	6.80	8.10	7.45		111.75			
	15.00	30.00		1	15.00	8.10	7.90	8.00		120.00			
	30.00	45.00		1	15.00	7.90	7.00	7.45		111.75			
	45.00	60.00		1	15.00	7.00	6.70	6.85		102.75			
	60.00	75.00		1	15.00	6.70	7.00	6.85		102.75			
	75.00	78.00		1	3.00	7.00	7.00	7.00		21.00			
	78.00	90.00		1	12.00	7.00	9.60	8.30		99.60			
	90.00	91.00		1	1.00	9.60	9.60	9.60		9.60			
	91.00	105.00		1	14.00	9.60	8.30	8.95		125.30			
	105.00	109.00		1	4.00	8.30	8.30	8.30		33.20			
	109.00	120.00		1	11.00	8.30	9.50	8.90		97.90			
	120.00	126.00		1	6.00	9.50	9.50	9.50		57.00			
	126.00	135.00		1	9.00	9.50	7.50	8.50		76.50			

BOQ Item No	Description Chainage		Side	Nos	Length	Width B1	Width B2	Width Avg B	Depth	Quantity	Unit/ Remarks	Rate
	135.00	143.50		1	8.50	7.50	7.50	7.50		63.75		
	143.50	150.00		1	6.50	7.50	9.90	8.70		56.55		
	150.00	165.00		1	15.00	9.90	9.20	9.55		143.25		
	165.00	180.00		1	15.00	9.20	9.20	9.20		138.00		
	180.00	185.00		1	5.00	9.20	9.20	9.20		46.00		
	185.00	195.00		1	10.00	9.20	9.20	9.20		92.00		
	195.00	208.00		1	13.00	9.20	9.20	9.20		119.60		
	208.00	210.00		1	2.00	9.20	8.80	9.00		18.00		
	210.00	220.00		1	10.00	8.80	8.80	8.80		88.00		
	220.00	225.00		1	5.00	8.80	8.70	8.75		43.75		
	225.00	240.00		1	15.00	8.70	9.30	9.00		135.00		
	240.00	245.00		1	5.00	9.30	9.30	9.30		46.50		
	245.00	250.00		1	5.00	9.30	9.30	9.30		46.50		
	250.00	253.00		1	3.00	9.30	7.10	8.20		24.60		
	253.00	255.00		1	2.00	7.10	7.10	7.10		14.20		
	255.00	270.00		1	15.00	7.10	5.90	6.50		97.50		
	270.00	285.00		1	15.00	5.90	7.20	6.55		98.25		
	285.00	300.00		1	15.00	7.20	7.00	7.10		106.50		
	300.00	315.00		1	15.00	7.00	6.30	6.65		99.75		
	315.00	330.00		1	15.00	6.30	6.40	6.35		95.25		
	330.00	345.00		1	15.00	6.40	6.50	6.45		96.75		
	345.00	360.00		1	15.00	6.50	6.30	6.40		96.00		
	360.00	375.00		1	15.00	6.30	5.90	6.10		91.50		
	375.00	390.00		1	15.00	5.90	6.00	5.95		89.25		
	390.00	405.00		1	15.00	6.00	6.00	6.00		90.00		
	405.00	417.00		1	12.00	6.00	7.00	6.50		78.00		
	Ganesh Nagar Road											
	0.00	15.00		1	15.00	5.70	5.40	5.55		83.25		
	15.00	30.00		1	15.00	5.40	6.00	5.70		85.50		
	30.00	45.00		1	15.00	6.00	6.40	6.20		93.00		
	45.00	60.00		1	15.00	6.40	6.50	6.45		96.75		
	60.00	75.00		1	15.00	6.50	8.10	7.30		109.50		
	75.00	90.00		1	15.00	8.10	6.60	7.35		110.25		
	90.00	105.00		1	15.00	6.60	4.60	5.60		84.00		
	105.00	120.00		1	15.00	4.60	4.50	4.55		68.25		
	120.00	135.00		1	15.00	4.50	4.30	4.40		66.00		
	135.00	150.00		1	15.00	4.30	6.20	5.25		78.75		
	150.00	165.00		1	15.00	6.20	4.70	5.45		81.75		
	165.00	180.00		1	15.00	4.70	5.30	5.00		75.00		
	180.00	195.00		1	15.00	5.30	5.30	5.30		79.50		
	195.00	210.00		1	15.00	5.30	4.10	4.70		70.50		
	210.00	225.00		1	15.00	4.10	6.70	5.40		81.00		
	225.00	240.00		1	15.00	6.70	6.00	6.35		95.25		
	240.00	255.00		1	15.00	6.00	6.10	6.05		90.75		
	255.00	270.00		1	15.00	6.10	6.30	6.20		93.00		
	270.00	285.00		1	15.00	6.30	8.40	7.35		110.25		
	285.00	300.00		1	15.00	8.40	10.20	9.30		139.50		
	300.00	315.00		1	15.00	10.20	15.20	12.70		190.50		
	315.00	330.00		1	15.00	15.20	18.90	17.05		255.75		
	330.00	338.50		1	8.50	18.90	20.30	19.60		166.60		
	8th C Cross Road Ganesh Nagar											
	0.00	15.00		1	15.00	6.60	6.70	6.65		99.75		
	15.00	30.00		1	15.00	6.70	7.30	7.00		105.00		
	30.00	45.00		1	15.00	7.30	7.90	7.60		114.00		
	45.00	60.00		1	15.00	7.90	7.10	7.50		112.50		
	60.00	75.00		1	15.00	7.10	5.30	6.20		93.00		
	75.00	90.00		1	15.00	5.30	6.50	5.90		88.50		
	90.00	105.00		1	15.00	6.50	7.40	6.95		104.25		
	105.00	115.00		1	10.00	7.40	2.40	4.90		49.00		
	115.00	120.00		1	5.00	2.40	5.30	3.85		19.25		
	120.00	140.00		1	20.00	5.30	5.70	5.50		110.00		
	140.00	150.00		1	10.00	5.70	4.60	5.15		51.50		
	150.00	171.00		1	21.00	4.60	6.30	5.45		114.45		

Item No	Description Chainage		Side	Nos	Length	Width B1	Width B2	Width Avg B	Depth	Quantity	Unit/ Remarks	Rate	Amount
	8th A Cross Road Ganesh Nagar												
	0.00	15.00		1	15.00	5.70	5.90	5.80		87.00			
	15.00	30.00		1	15.00	5.90	6.20	6.05		90.75			
	30.00	45.00		1	15.00	6.20	7.30	6.75		101.25			
	45.00	65.80		1	20.80	7.30	7.10	7.20		149.76			
	8th A Cross Road Opp Road Ganesh Nagar												
	0.00	15.00		1	15.00	7.20	7.30	7.25		108.75			
	15.00	35.30		1	20.30	7.30	7.30	7.30		148.19			
	8th B Cross Road Ganesh Nagar												
	0.00	15.00		1	15.00	6.60	6.20	6.40		96.00			
	15.00	30.00		1	15.00	6.20	5.40	5.80		87.00			
	30.00	45.00		1	15.00	5.40	5.20	5.30		79.50			
	45.00	66.00		1	21.00	5.20	7.50	6.35		133.35			
	8th B Cross Road Opp Raod Ganesh Nagar												
	0.00	15.00		1	15.00	7.50	5.90	6.70		100.50			
	15.00	30.00		1	15.00	5.90	7.10	6.50		97.50			
	30.00	33.50		1	3.50	7.10	7.10	7.10		24.85			
	2nd Main Road 7th A Cross Ganesh Nagar												
	0.00	15.00		1	15.00	6.30	5.00	5.65		84.75			
	15.00	30.00		1	15.00	5.00	5.50	5.25		78.75			
	30.00	45.00		1	15.00	5.50	5.90	5.70		85.50			
	45.00	60.00		1	15.00	5.90	5.90	5.90		88.50			
	60.00	75.00		1	15.00	5.90	5.80	5.85		87.75			
	75.00	90.00		1	15.00	5.80	5.80	5.80		87.00			
	90.00	105.00		1	15.00	5.80	5.50	5.65		84.75			
	105.00	119.20		1	14.20	5.50	5.90	5.70		80.94			
	Alpine Pyrmaid Road												
	0.00	15.00		1	15.00	9.50	7.80	8.65		129.75			
	15.00	30.00		1	15.00	7.80	6.50	7.15		107.25			
	30.00	36.50		1	6.50	6.50	6.30	6.40		41.60			
	Dhanlakshmi Enclave												
	0.00	15.00		1	15.00	7.70	5.80	6.75		101.25			
	15.00	30.00		1	15.00	5.80	5.40	5.60		84.00			
	30.00	45.00		1	15.00	5.40	5.50	5.45		81.75			
	45.00	60.00		1	15.00	5.50	6.00	5.75		86.25			
	60.00	75.00		1	15.00	6.00	6.50	6.25		93.75			
	75.00	90.00		1	15.00	6.50	5.90	6.20		93.00			
	90.00	100.00		1	10.00	5.90	6.80	6.35		63.50			
	Continuatation												
	0.00	15.00		1	15.00	4.80	4.80	4.80		72.00			
	15.00	30.00		1	15.00	4.80	3.60	4.20		63.00			
	30.00	45.00		1	15.00	3.60	3.50	3.55		53.25			
	45.00	48.50		1	3.50	3.50	3.40	3.45		12.08			
	1st Main Road KVS Badavane												
	0.00	15.00		1	15.00	3.80	3.00	3.40		51.00			
	15.00	30.00		1	15.00	3.00	4.50	3.75		56.25			
	30.00	45.00		1	15.00	4.50	5.40	4.95		74.25			
	45.00	60.00		1	15.00	5.40	5.90	5.65		84.75			
	60.00	75.00		1	15.00	5.90	5.60	5.75		86.25			
	75.00	90.00		1	15.00	5.60	4.60	5.10		76.50			
	90.00	105.00		1	15.00	4.60	5.20	4.90		73.50			
	105.00	115.00		1	10.00	5.20	5.60	5.40		54.00			
	1st Cross Road												
	0.00	15.00		1	15.00	5.20	5.50	5.35		80.25			
	15.00	30.00		1	15.00	5.50	4.60	5.05		75.75			
	30.00	45.00		1	15.00	4.60	4.40	4.50		67.50			
	45.00	60.00		1	15.00	4.40	4.50	4.45		66.75			

BOQ Item No	Description		Side	Nos	Length	Width			Depth	Quantity	Unit/ Remarks	Rate	
	Chainage					B1	B2	Avg B					
	60.00	68.00		1	8.00	4.50	4.70	4.60		36.80			
	2nd Cross Road												
	0.00	15.00		1	15.00	5.00	4.10	4.55		68.25			
	15.00	30.00		1	15.00	4.10	4.40	4.25		63.75			
	30.00	45.00		1	15.00	4.40	4.70	4.55		68.25			
	45.00	57.00		1	12.00	4.70	4.80	4.75		57.00			
	2nd A Cross Road												
	0.00	15.00		1	15.00	5.10	4.20	4.65		69.75			
	15.00	18.50		1	3.50	4.20	4.40	4.30		15.05			
	2nd B Cross Road												
	0.00	15.00		1	15.00	4.60	4.20	4.40		66.00			
	15.00	30.00		1	15.00	4.20	4.60	4.40		66.00			
	30.00	45.00		1	15.00	4.60	5.00	4.80		72.00			
	45.00	53.00		1	8.00	5.00	5.40	5.20		41.60			
								Deduct Prime Coat		**-1095.64**			
								Total Quantity		**31959.46**	**Sqm**	**5.10**	16299
7	KSRRB 500-7. Providing and applying tack coat using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH/Chapter 5 Page No. 158/ Item No. 21.7/ PWD SR 2018-19 Issue Rates												
	Tackcoat For DBM												
	Virupakshanagar 5th cross road.												
	0.00	15.00		1	15.00	6.80	5.90	6.35		95.25			
	15.00	30.00		1	15.00	5.90	5.90	5.90		88.50			
	30.00	45.00		1	15.00	5.90	5.80	6.00		90.00			
	45.00	60.00		1	15.00	6.30	5.80	6.05		90.75			
	60.00	75.00		1	15.00	5.80	5.40	5.60		84.00			
	75.00	90.00		1	15.00	5.40	5.40	6.00		90.00			
	90.00	105.00		1	15.00	5.40	5.70	5.55		83.25			
	105.00	120.00		1	15.00	5.70	5.70	5.70		85.50			
	120.00	135.00		1	15.00	5.70	5.60	5.65		84.75			
	135.00	150.00		1	15.00	5.60	5.60	5.60		84.00			
	150.00	165.00		1	15.00	5.60	4.90	5.25		78.75			
	165.00	180.00		1	15.00	4.90	4.90	4.90		73.50			
	180.00	195.00		1	15.00	4.90	5.20	5.05		75.75			
	195.00	210.00		1	15.00	5.20	5.20	5.20		78.00			
	210.00	214.00		1	4.00	5.20	5.30	5.25		21.00			
	Virupakshanagar 4th cross road.												
	0.00	15.00		1	15.00	6.10	6.30	6.20		93.00			
	15.00	30.00		1	15.00	6.30	6.30	6.30		94.50			
	30.00	45.00		1	15.00	6.30	5.90	6.00		90.00			
	45.00	60.00		1	15.00	6.30	5.90	6.10		91.50			
	60.00	75.00		1	15.00	5.90	5.30	5.60		84.00			
	75.00	90.00		1	15.00	5.30	5.30	6.00		90.00			
	90.00	105.00		1	15.00	5.30	4.60	4.95		74.25			
	105.00	120.00		1	15.00	4.60	4.60	4.60		69.00			
	120.00	135.00		1	15.00	4.60	4.30	4.45		66.75			
	135.00	150.00		1	15.00	4.30	4.30	4.30		64.50			
	150.00	165.00		1	15.00	4.30	4.40	4.35		65.25			
	165.00	180.00		1	15.00	4.40	4.40	4.40		66.00			
	180.00	195.00		1	15.00	4.40	4.60	4.50		67.50			
	195.00	208.00		1	13.00	4.60	4.60	4.60		59.80			
	Virupakshanagar 3rd cross road.												
	0.00	15.00		1	15.00	8.10	6.40	7.25		108.75			
	15.00	30.00		1	15.00	6.40	6.40	6.40		96.00			
	30.00	45.00		1	15.00	6.40	5.60	6.00		90.00			

Q Item No	Description
	Chainage
	45.00 60.00
	60.00 75.00
	75.00 90.00
	90.00 105.00
	105.00 120.00
	120.00 135.00
	135.00 150.00
	150.00 165.00
	165.00 180.00
	180.00 195.00
	195.00 210.00
	210.00 225.00
	225.00 240.00
	240.00 255.00
	255.00 270.00
	270.00 285.00
	285.00 300.00
	300.00 308.00
	308.00 310.00
	310.00 325.00
	325.00 330.00
	Profile correction
	8th Main Deshab
	30.00 57.00
	7th Main Deshab
	60.00 82.00
	100.00 118.00
	4th main Deshab
	0.00 36.00
	3rd main Deshab
	55.00 85.00
	2nd Main Road D
	25.00 45.00
	55.00 75.00
	Renukamba Tem
	0.00 20.00
	55.00 86.00
	135.00 160.00
	3rd Cross Road C
	15.00 26.00
	50.00 65.00
	2nd Main Road
	0.00 31.00
	65.00 100.00
	2nd B cross Rami
	50.00 95.00
	5th Main Deshaba
	40.00 75.00
	100.00 110.00
	2nd Cross Byrapp
	0.00 18.00
	110.00 145.00
	Family Enclave Ro
	55.00 80.00

BOQ Item No	Description Chainage		Side	Nos	Length	Width B1	Width B2	Width Avg B	Depth	Quantity	Unit/ Remarks	Rate	Amount
	45.00	60.00		1	15.00	6.30	5.60	5.95		89.25			
	60.00	75.00		1	15.00	5.60	5.20	5.40		81.00			
	75.00	90.00		1	15.00	5.20	5.20	6.00		90.00			
	90.00	105.00		1	15.00	5.20	5.90	5.55		83.25			
	105.00	120.00		1	15.00	5.90	5.90	5.90		88.50			
	120.00	135.00		1	15.00	5.90	5.50	5.70		85.50			
	135.00	150.00		1	15.00	5.50	5.50	5.50		82.50			
	150.00	165.00		1	15.00	5.50	5.20	5.35		80.25			
	165.00	180.00		1	15.00	5.20	5.20	5.20		78.00			
	180.00	195.00		1	15.00	5.20	8.20	6.70		100.50			
	195.00	210.00		1	15.00	8.20	8.20	8.20		123.00			
	210.00	225.00		1	15.00	8.20	6.20	7.20		108.00			
	225.00	240.00		1	15.00	6.20	6.20	6.20		93.00			
	240.00	255.00		1	15.00	6.20	6.30	6.25		93.75			
	255.00	270.00		1	15.00	6.30	6.30	6.30		94.50			
	270.00	285.00		1	15.00	6.30	7.50	6.90		103.50			
	285.00	300.00		1	15.00	7.50	7.50	7.50		112.50			
	300.00	308.00		1	8.00	7.50	7.50	7.50		60.00			
	308.00	310.00		0						0.00	culvert		
	310.00	325.00		1	15.00	0.00	7.30	3.65		54.75			
	325.00	330.00		1	5.00	7.30	7.30	7.30		36.50			
	Profile correction												
	8th Main Deshabandu nagar												
	30.00	57.00		1	27.00	2.00	1.50	1.75		47.25			
	7th Main Deshabandu nagar												
	60.00	82.00		1	22.00	2.20	1.50	1.85		40.70			
	100.00	118.00		1	18.00	2.00	1.70	1.85		33.30			
	4th main Deshabandu nagar												
	0.00	36.00		1	36.00	1.80	2.00	1.90		68.40			
	3rd main Deshabandu nagar												
	55.00	85.00		1	30.00	1.50	1.50	1.50		45.00			
	2nd Main Road Deshabandu nagar												
	25.00	45.00		1	20.00	1.80	1.50	1.65		33.00			
	55.00	75.00		1	20.00	1.20	1.50	1.35		27.00			
	Renukamba Temple Road												
	0.00	20.00		1	20.00	1.80	1.50	1.65		33.00			
	55.00	86.00		1	31.00	1.20	1.50	1.35		41.85			
	135.00	160.00		1	25.00	1.20	1.50	1.35		33.75			
	3rd Cross Road G Byrappa Garden												
	15.00	26.00		1	11.00	1.80	1.50	1.65		18.15			
	50.00	65.00		1	15.00	1.20	1.50	1.35		20.25			
	2nd Main Road												
	0.00	31.00		1	31.00	1.20	1.50	1.35		41.85			
	65.00	100.00		1	35.00	1.20	1.50	1.35		47.25			
	2nd B cross Ramiah Garden												
	50.00	95.00		1	45.00	1.10	1.50	1.30		58.50			
	5th Main Deshabandu nagar												
	40.00	75.00		1	35.00	1.50	2.00	1.75		61.25			
	100.00	110.00		1	10.00	1.50	2.00	1.75		17.50			
	2nd Cross Byrappa Garden												
	0.00	18.00		1	18.00	1.50	2.00	1.75		31.50			
	110.00	145.00		1	35.00	1.10	1.80	1.45		50.75			
	Family Enclave Road												
	55.00	80.00		1	25.00	1.10	1.80	1.45		36.25			